

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>31</u> T. <u>1</u> N. <u>1</u> R. <u>1</u> E.		<u>A-13</u>
2. PROPERTY CONTROLLING IN SECTION <u>31</u> T. <u>1</u> N. <u>1</u> R. <u>1</u> E.		<u>A-13</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. _____ R. _____ E.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, _____ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on June 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on June 1974, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

A-13 set corner
 S 61 1/2° E 20 LINKS 16" ELM
 N 42° E 18 LINKS 9" ELM

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

A-13 Found pointed stone set by Aaron Jackson in 1856. Replaced with 20' dia. concrete monument with 2' dia. Brass cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

✓ A-13
 20' dia. concrete monument with 2' dia. Brass cap
 S 78° E 31.16' Clump 5 Maple
 S 00° 07' 36" W 50.0' concrete monument 12" dia., 18" high
 S 89° 31' 09" E 50.0' concrete monument 12" dia., 18" high
 N 30° W 42.30' 8" Maple

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12009 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____