

SURVEY &
 REMONUMENTATION
 APR 10 1995
 COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 LESLIE

LIBER 8 PAGE 191

FILED

For corners in
INGHAM
(County)

Located In: _____ Corner Code # _____

- | | | | | | |
|------------------------------------|---|-----------|---|-----------|------------|
| 1. Public Land Survey | T | <u>1N</u> | R | <u>1W</u> | <u>H-4</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

JUL 15 2 23 PM '94

REGISTER OF DEEDS
 INGHAM COUNTY MICH

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, RON HELSEL, in a field survey on OCT. 19, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 CORNER NOT SET IN ORIGINAL GOVERNMENT SURVEY.

- 1). A SURVEY WAS RECORDED IN VOL. 2, PG. 259 & IN VOL. 5, PG. 50 BY R.J. ROBB, APRIL 7, 1907. ROBB CALLED FOR AN IRON BOLT, ELM 16" S10W, 26-1/23 LINKS
 ELM 15" S87E, 38-1/2 LINKS

(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND BRYANS 1/2" IRON BAR & CAP #25832 NEXT TO A HORIZONTAL ANGLE IRON FENCE POST. NO FENCES EXIST ANY MORE AND ALL (3) OF HIS BEARING TREES ARE ROTTED STUMPS. EXCAVATED A 3 FOOT BY 2 FOOT DEEP HOLE AROUND HIS 1/2" BAR AND FOUND THE REMAINS OF AN OLD ANCHOR POST. ACCEPTED THE POSITION OF HIS MARKER & SET A 3/4" BY 24" STEEL FORM PIN WITH A CAP LABELED P.A. 345.
 RECORDED BRYAN DATUM: H-4 TO G-4, 2644.16'
 H-4 TO H-3, 2657.60'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 3/4" X 24" FORM PIN AND CAP
 SET GALV. NAIL & CAP #18994, E/SIDE 12" ELM, S22°E, 17.58'
 SET GALV. NAIL & CAP #18994, N/SIDE 14" ELM, N85°E, 46.52'
 SET GALV. NAIL & CAP #18994, SE/SIDE 10" ELM, N17°E, 13.89'
 SET GALV. NAIL & CAP #18994, W/SIDE 20" MAPLE, N24°W, 39.79'



Signed by Ron Helsel Date JULY 13, 1994
 Surveyor's Michigan License No. 18994

"A" CONTINUED

- 2). A C.R.C. WAS RECORDED IN LIBER 5; PG. 381, FIELD DATED DEC. 31, 1979 BY L. BRYAN #25832. "FD. REMAINS OF WOOD ANCHOR POST AT EXTENDED INTERSECTION OF EAST, WEST AND SOUTH FENCES. ALSO FD. 2' LONG IRON BOLT LYING NEXT TO ANCHOR POST. MEASURED IN CLOSE ACCORD WITH R.J. ROBB SURVEY (VOL. 2, PG. 259) TO THE NORTH AND WEST. ACCEPTED LOCATION OF ANCHOR POST AS CORNER".
SET 1/2" BAR & CAP IN CENTER OF ANCHOR POST
SET NAIL & TAG WEST SIDE 30" MAPLE, SOUTH, 19.73'
SET NAIL & TAG NORTH SIDE 30" MAPLE, EAST, 44.93'
SET NAIL & TAG WEST SIDE 30" MAPLE, S30°W, 40.10'
- 3). A SURVEY RECORDED BY L. BRYAN RECORDED IN LIBER 3, PGS. 1102-1105, DATED 12-31-79 GAVE THE SAME WITNESSES AND MONUMENT AS HIS C.R.C. ABOVE.

DID NOT FIND FURTHER MENTION OF THIS CORNER IN PUBLIC OR PRIVATE RECORDS.