

J-3, T1N, R1W

Part A - Continued

- 5). 06-07-1973: Certified Survey Map (Rec. 8-21-73, L1-P859), R. M. Lester, P.S. 18998 calls for the same monument and witnesses as given in Item 2 above. The drawing shows a distance of 2653.76 feet to J-4.
- 6). June 1987: Certified Survey Map (Rec. 6-30-87, L5-P238), and Certified Survey Map (Rec. 6-30-87, L5- P240), R. M. Lester notes "½" bar and cap, L1-P399: nail and tag in North side 10" Shag Bark Hickory S.E. 13.4', nail and tag in North side 30" Shag Bark Hickory East 54.0', nail and tag in West side 12" Oak S.E. 7.7', nail and ribbon on North side 28" Maple West 21.7'." The drawing shows a distance of 2653.76 feet to J-4.
- 7). March 1989: Certified Survey Map (Rec. 4-03-89, L5- P1030), R. M. Lester notes "½" bar and cap, L1-P399: nail and tag in North side 10" Shag Bark Hickory S.E. 13.4', nail and tag in North side 30" Shag Bark Hickory East 54.0', nail and tag in West side 12" Oak S.E. 7.7', nail and ribbon on North side 28" Maple West 21.7'." The drawing shows a distance of 2653.76 feet to J-4.
- 8). 03-20-1991: Certified Survey Map (Rec. 12-09-91, L6-P881), Ron Helsel, P.S. 18994 notes "Found ½" Iron" and lists the same witnesses as given in Item 2 above. The drawing shows distances of 2657.15 feet to J-2 and 2664.41 feet to I-3.
- 9). 09-19-1996: Certified Survey Map (Rec. 11-22-96, L7-P940), M. H. Mahieu, P.S. 28414 calls for the South 1/4 Corner of Section 2, T1N, R1W, but gives no monument description nor witnesses. The drawing shows a distance of 2657.15 feet to J-2.