

DEC 1 2 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 274

For corners in LESLIE TOWNSHIP

INGHAM COUNTY

Located In: Corner Code #

- 1. Public Land Survey T 1N R 1W K-1
2. Property Controlling in Section S
3. Miscellaneous Property in Sec. S

FILED

970047744
12/02/1997 13:38:14
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

- 4. Lot No. , Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

Table with columns A-M and rows 1-13 containing numerical data for the Register of Deeds stamp.

I, Maurice H. Mahieu, in a field survey on September 25, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. GLO notes state "79.82 intersection North boundary 115.2 West of Post, Hickory 12 S 51 1/2 E 13, Hickory 7 S 70W 38, survey performed by Hervey Parke, Deputy Surveyor, in February 1826.
2. County Surveyor A. Jackson, on Jan. 16, 1843, recorded in Vol. 1, Page 10; Hick 12 S 51 1/2 E 13 links; Hick 7 S 70W 38 1/2 links.
3. County Surveyor W. A. Rowe, on May 10, 1896, called for corner to be "stone and brick", W. Oak 12 N-W 33 3/4 lks, Walnut 4 SE 43 3/4 lks. Recorded in Book 3 Page 199.
4. Ronnie Lester, P.S. #18998, recorded L.C.R.C. on Sept. 5, 1978 in Liber 4, Page 334, stated "Found 4"x 7" x 14" Blue Rock, 18" below surface. Found 1.5" x 2" x 6" long stone with brick, 32" below road surface, beneath found blue rock, +/- 1' West of extended fence/tree line to South and +/- 2' North of centerline Plains Road. Found plow point 40" below surface and beneath found blue rock and long stone with brick. Accepted long stone with brick as corner described by W. A. Rowe." Lester set 4" x 36" concrete monument with 1/2" x 38" rered with cap #18998 in location of long stone, with the following witnesses: Nail and Tag #18998 South Side 20" Twin Oak, ENE 85.55'; Nail and Tag #18998 North side 48" Oak, WSW 82.72'; Nail and Tag #18998 NW side 8" Ash, SW 47.11'; Nail and Tag #18998 West side 48" Oak, NW 23.80'; T-Bar, K-13, Vevay Twp., T2N, R1W, East, 73.06'.
5. Ron Helsel, P.S. #18994, recorded P.A. 132 survey on Nov. 12, 1990 in Liber 6, Pages 548-550, Helsel stated corner to be concrete monument with the following witnesses: Set Nail and Tag South Side Twin 16" Oak, ENE 85.00'; Found Nail and Tag, North Side 48" Oak, WSW 82.72'; Found Nail and Tag, West side 48" Oak, NW 23.80'; Southwest Corner, Section 36, T2N, R1W, East 73.06'. Measured 2647.91 to K-2.
6. Ronnie Lester, P.S. #18998, recorded P.A. 132 survey on May 10, 1996 in Liber 7, Pages 785-786, Lester stated corner to be concrete monument and cap with the following witnesses: Found Nail and Tag #18998 North side 50" Oak Mag Az. 255°, 82.69'; Found Nail and Tag #18998 West side 50" Oak Mag Az. 345°, 23.84'; Northeast Corner House Foundation Mag Az. 216° 120.48'; T-Bar, K-13, Vevay Mag Az. 98° 73.06'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron concrete monument with damaged cap. Monument falls 2' +/- North of centerline Plains Road on tree line to South. Found following witnesses. Nail and Tag #18998 West side 48" Oak N 20° W 23.80'; K-13, Vevay Twp., T2N, R1W, S 85° E, 73.15'; Accepted monument as being in the correct location from previous excavation performed by Ronnie Lester in 1978. Set cap stamped #28414 on monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" Iron Rod concrete monument with cap #28414 in monument box, Witnesses: Set Nail and Tag #28414 Southwest side 48" Oak, N 20° W 22.83' Set Nail and Tag #28414 North side 11' Walnut, S 60° W 32.27' Set Nail and Tag #28414 East side 10" Basswood, S 20° E 30.70' Set Nail and Tag #28414 South side 6" Ash, N 45° E 36.64' K-13, Vevay Twp., T2N, R1W, S 85° E 73.15'

Signed by Maurice H. Mahieu
Surveyor's Michigan License No. 28414

Date 11-25-97

