

REMONUMENTATION

DEC 1 2 1997

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Liber

9 Page 282

For corners in **COMMISSION**  
LESLIE TOWNSHIP  
INGHAM COUNTY

	Located In:	Corner Code #
1. Public Land Survey	T <u>1N</u> R <u>1W</u>	<u>M-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**FILED**

970047749  
12/02/1997 13:38:24  
REGISTER OF DEEDS  
Paula Johnson  
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Maurice H. Mahieu, in a field survey on September 15, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	P
1													
2		6		5		4		3		2		1	4
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:  
1. ORIGINAL G.L.O. CORNER WAS SET BY JOSEPH WAMPLER D. S. IN MAY 1825 \*40.00 SET 1/4 SEC. POST; B. OAK ---- N28 1/2W 32, TAM 8 S76W 27 1/2'

2. COUNTY SURVEYOR A. JACKSON DID A SURVEY IN NOVEMBER 1841. SURVEY IS IN VOL. 1, PAGE 113. NO MENTION OF CORNER MATERIAL. WITNESSES: "B. OAK 9 N28 1/2W 32 LKS, TAMARACK 8 S76W 27 1/2 LKS" (THIS INFORMATION WAS TRANSCRIBED FROM COUNTY SURVEYORS RECORD IN VOL 4A, PAGE 112 TO 1979 CETA REMONUMENTATION NOTES)

(See Back for continuation)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND 1/2" SMOOTH IRON PIPE WITH YELLOW CAP (UNREADABLE) IN MONUMENT BOX AT INTERSECTION OF KELLY AND VAUGHN ROADS. FOUND THE FOLLOWING WITNESSES: NAIL & TAG #25832, WEST SIDE 32" WALNUT, S14°E, 91.73'; CENTERLINE 18" HICKORY, N59°E, 45.3'. 1/2" PIPE IN GOOD CONDITION AND LEFT IN PLACE. Accepted position of 1/2" pipe as the perpetuated position of corner based on investigation of corner by Richard W. Steadman, P.S. 11370.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
1/2" SMOOTH IRON PIPE, WITNESSED BY:

- SET NAIL & TAG #28414, SOUTH SIDE 18" CHERRY, N59°E, 45.27 FEET
- SET NAIL & TAG #28414, EAST SIDE UTILITY POLE, N45°W, 65.48 FEET
- SET NAIL & TAG #28414, NORTH SIDE 21" WALNUT, S81°W, 108.15 FEET
- FND. NAIL & TAG #25832, WEST SIDE 32" WALNUT, S14°E, 91.73 FEET



Signed by Maurice H. Mahieu  
Surveyor's Michigan License No. 28414

Date 10-10-97

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975

REVISED JAN., 1983  
REVISED OCT., 1995

P.A. 345 INGHAM COUNTY  
PEER APPROVED 9/25/97 M

M-2 Continued  
Page 2

3. LCRC IN LIBER 4, PAGE 265 DATED JULY 29, 1978 BY RICHARD W. STEADMAN, P.S. 11370. FOUND A RAILROAD SPIKE IN THE INTERSECTION OF VAUGHN AND KELLY ROADS, DUG HOLE, AND BELOW RAILROAD SPIKE ABOUT 2 FEET DEEP, FOUND WELL ROTTED WOOD STAKE. RAISED LOCATION OF WOOD STAKE TO SURFACE WITH 1/2" IRON PIPE. WITNESSED BY:  
 10" HICKORY N.E. 45.61 FEET  
 TELEPHONE POLE, S.E. 53.98 FEET  
 28" WALNUT, S.S.E., 91.79 FEET  
 C/L 2" STEEL ROAD SIGN POST, S.W. 36.97 FEET
  
4. LCRC IN LIBER 5, PAGE 151 DATED JAN 16, 1979 BY AUSTIN C. WILLIAMS, P.S. 21275. "FOUND 3/4" IRON ROD IN CENTERLINE OF KELLY & VAUGHN ROADS. MEASUREMENTS NORTH & SOUTH IN CLOSE ACCORD WITH GLO RECORDS. WITNESSED BY:  
 NAIL & TAG 18" ASH N70°E 46.31'  
 NAIL & TAG 30" WALNUT S20°E 91.85'  
 CENTERLINE 2" STEEL SIGN POST S35°W 36.88"
  
5. AN ACT 132 SURVEY RECORDED IN LIBER 3, PAGE 706 BY AUSTIN C. WILLIAMS, P.S. 21275 CALLS FOR EAST 1/4 CORNER OF SECTION 1; NO MENTION OF CORNER MATERIAL. WITNESSES:  
 NAIL & TAG 18" ASH N70°E 46.31'  
 NAIL & TAG 30" WALNUT S20°E 91.85'  
 CENTERLINE 2" STEEL SIGN POST S35°W 36.88'
  
6. AN ACT 132 SURVEY RECORDED IN LIBER 6, PAGE 196 BY LARRY BRYAN, P.S. 25832 CALLS FOR EAST 1/4 CORNER AS A FOUND PIPE AND CAP CENTERLINE OF KELLY & VAUGHN ROADS, LIBER 4, PAGE 265. WITNESSED BY:  
 FOUND NAIL & TAG NORTH SIDE 20" WALNUT, S80°W 108.86'  
 SET NAIL & TAG WEST SIDE 36" WALNUT, S25°E 91.79'  
 SET NAIL & TAG SOUTH SIDE 18" HICKORY, N50°E, 45.61'
  
7. AN ACT 132 SURVEY RECORDED IN LIBER 7, PAGE 372 BY LARRY BRYAN, P.S. 25832 CALL FOR EAST 1/4 CORNER, SECTION 1, T1N, R1W, LIBER 5, PAGE 151. "FOUND 1/2" PIPE WITH CAP AT INTERSECTION OF VAUGHN & KELLY ROADS.  
 FOUND NAIL & TAG EAST SIDE 15" HICKORY, NE 45.67'  
 FOUND NAIL & TAG #25832, WEST SIDE 30" WALNUT, SSE, 91.79'  
 FOUND NAIL & TAG, NORTH SIDE 14" WALNUT, S70°W, 108.84'  
 CENTERLINE ROAD SIGN POST, N45°W, 38.09"

