

DEC 12 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 284

For corners in LESLIE TOWNSHIP

INGHAM COUNTY

Located In:

Corner Code #

- 1. Public Land Survey T 1N R 1W M-3
2. Property Controlling in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

FILED

970067750
12/02/1997 13:38:25
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

I, Maurice H. Mahieu, in a field survey on September 23, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Table with 13 columns (A-M) and 13 rows (1-13) containing numerical data for the Register of Deeds Stamp.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. GLO notes states "80.00 Set Post Cor. Secs. 1 & 12, W. Oak 30 N 11W, 89, W. Oak 24 S 43W 67" Survey performed by Hervey Parke, Deputy Surveyor, in February 1826.
2. Ronnie Lester, P.S. #18998, recorded a P.A. 132 survey on Oct. 29, 1973 in Liber 1, Page 994-995. Lester gives no description of corner monumentation, but states following three witnesses: Set Nail & Tag West side 15" Wild Cherry, NNE, 30.60'; Set Nail & Tag NW side 10" Twin Wild Cherry, NE, 25.27'; Set Nail & Tag North side 10" Apple, SW, 32.51'. Measured 2645.26 to M-4.
3. Ronnie Lester, P.S. #18998, recorded L.C.R.C. on Jan. 3, 1974, in Liber 2, Page 613. Lester states "Found 1" Axle set in stones on wood line South, distances West and South in close accord with original government monument." Lester recorded three witnesses which are the same as A-2.
4. Austin Williams, P.S. #21275, recorded P.A. 132 survey, on Jan. 16, 1979, in Liber 3, Page 706, Williams gives no description of corner monumentation, but states the following three witnesses: Nail & Tag W/S 15" Cherry, NNE, 30.60'; Nail & Tag NW/S 10" Twin Cherry, NE 25.27'; Nail and Tag N/S 10" Apple SW 32.51'. Measured 2658.61 to M-2.
5. Ingham County Remonumentation CETA project of 1979-81 with Technical Supervisor Ronnie Lester, P.S. #18998 did a section breakdown of Section 1. Final date of survey is May 21, 1981. Measurements from M-3 to M-2 is 2656.95 ft.; M-3 to L-3 is 2657.08 ft.

(Continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" x 5' ± Axle shaft surrounded by pile of stone with the following witnesses:

- Nail and Tag #25832 South Side 30" Ash, East 33.15'
Nail and Tag #25832 West Side 18" Ash, South 43.02'
Nail and Tag #25832 West Side 18" Ash, S 45° W 30.65'

The history of the found axle shaft is unknown. However, many surveys have used this axle shaft and has been assumed to be the corner by previous surveyors. There is no other evidence to dispute the location and this surveyor accepts the axle as the perpetuated location of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set standard 3/4" iron rod and cap stamped "P.A. 345 P.S. #28414 in place of 1" axle shaft. Witnesses:
Set Nail and Tag #28414 North Side 8" Triple Maple, S 45° E 15.89'
Set Nail and Tag #28414 North Side 16" Ash, S 80° W 33.05'
Set Nail and Tag #28414 West Side 14" Twin Ash, N 30° E 24.95'
Set Nail and Tag #28414 West Side 12" Elm, N 30° W 36.44'

Signed by Maurice H. Mahieu
Surveyor's Michigan License No. 28414

Date 11-25-97



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS JAN 1997
REVISED MAY 1995 REVISED JAN. 1998 REVISED OCT., 199

(A - Continued)

6. Unrecorded survey by Larry Bryan P.S. #25832 on June 6, 1995 notes corner as found axle shaft in rock pile on Tree line South, witnessed by:
Found Nail and Tag Northwest side Twin 10" Cherry N 45° E 25.25'
Set Nail and Tag South Side 24" Maple East 33.10'
Set Nail and Tag West Side 12" Cherry S 35° W 30.40'
Set Nail and Tag West Side 10" Cherry South 42.89'
Measured 2657.61 to M-2, 2657.73 to L-3, and 2645.49 to M-4.

7. Ingham County Remonumentation CETA project of 1979-81 with Technical Supervisor Ronnie Lester, P.S. #18998 did a section breakdown of Section 1. Final date of survey is May 21, 1981. Measurements from M-3 to M-2 is 2656.95 feet; M-3 to L-3 is 2657.08.