

DEC 1 2 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 265

For corners in

INGHAM COUNTY  
(County)  
STOCKBRIDGE TOWNSHIP

Located In: Corner #

1. Public Land Survey		<u>T 1N R 2E</u>	<u>A-3</u>
		T _____	_____
		T _____	_____
		T _____	_____
2. Property Controlling in Section	S _____	T _____	_____
	S _____	T _____	_____
3. Miscellaneous	S _____	T _____	_____
Property in Sec.	S _____	T _____	_____

FILED

970044057  
11/05/1997 12:39:51  
REGISTER OF DEEDS  
Paula Johnson  
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, DAVID L. CLIFFORD, in a field survey on OCTOBER 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. JOSEPH WAMPLER D.S. SET POST FOR M-3, T1N, R1E, IN ORIGINAL GOVERNMENT SURVEY IN FEBRUARY 1824: ASPEN 12" N½W 1077LKS; NO OTHER TREE.
2. SYLVESTER SIBLEY D.S. SET POST 100 LINKS (66') SOUTH OF M-3, T1N, R1W, IN ORIGINAL GOVERNMENT SURVEY: "NO TREES FOR BEARINGS, IN MARSH"
3. E.A. CALKINS, COUNTY SURVEYOR, STATES THAT HE STAKED CENTERLINE OF DOUGLAS DRAIN ON THE SECTION LINE BETWEEN SECTIONS 6 & 7 BUT DOES NOT MENTION CORNER WHEN LINE IS DESCRIBED IN THE MINUTES OF SURVEY FOR THE DOUGLAS DRAIN.
4. W.E. ZIMMER PE OF WOLVERINE ENGINEERS & SURVEYORS CALLS FOR CORNER TO FALL AT THE POINT WHERE THE DOUGLAS DRAIN TURNS NORTH IN A SURVEY PERFORMED IN OCTOBER 1968.
5. MAHIEU, LPS # 28414 SET A 1½" PIPE AT THE INTERSECTION OF DITCHES NORTH & EAST BASED ON THE DISTANCES RECORDED BY ZIMMER ON HIS 1968 SURVEY.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND A 1¼" PIPE 13.2' SOUTH OF ANOTHER 1¼" PIPE RECORDED IN LIBER 4 PAGE 14 AS M-3 T1N, R1E. AFTER TRAVERSEING ALL OF SECTIONS 6 & 7 OF STOCKBRIDGE TOWNSHIP AND SECTION 12 OF BUNKERHILL TOWNSHIP THIS SURVEYOR WAS CONVINCED THAT NEITHER PIPE MARKED EITHER OF THE CORNER POSITIONS ESTABLISHED BY THE GOVERNMENT SURVEY IN 1824 & 1825. REESTABLISHED M-3 BUNKERHILL BY SINGLE PROPORTIONATE MEASUREMENT AND SET A-3 STOCKBRIDGE 66' (THE GLO FALLING) SOUTH OF IT. IT IS MY OPINION THAT THESE POSITIONS ARE VERY CLOSE TO THE POSITIONS OF THE CORNERS AS THEY WERE ORIGINALLY ESTABLISHED. SET 1¼" GALVANIZED PIPE WITH PA 345 CAP IN EAST EDGE OF DRAIN FROM SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-3 T1N, R2E
- 1¼" GALVANIZED STEEL PIPE & YELLOW PLASTIC CAP IMPRINTED PA 345 PS 25837 IN EAST EDGE DRAIN
  - FOUND NAIL & TAG #28414 SOUTH SIDE 15" MULTIPLE BOX ELDER, 265° NAZ, 23.55'
  - SET NAIL & TAG #25837 EAST SIDE 12" ELM, 226° NAZ, 33.25'
  - FOUND NAIL & TAG #28414 WEST SIDE 6" POPLAR, 07° NAZ, 59.93'
  - SET NAIL & TAG #25837 EAST SIDE 16" POPLAR, 346° NAZ, 32.81'
  - SET NAIL & TAG #25837, EAST SIDE 15" WILLOW, 342° NAZ, 40.32'
  - 1¼" GALVANIZED STEEL PIPE & CAP (M-3, T1N, R1E), 0° NAZ, 66.00'
  - 1¼" GALVANIZED STEEL PIPE (PROPERTY CONTROLLING CORNER), 0° NAZ, 43.63'
  - 1¼" GALVANIZED STEEL PIPE (PROPERTY CONTROLLING CORNER), 0° NAZ, 30.43'



Signed by David L. Clifford  
Surveyor's Michigan License No. 25837

Date OCTOBER 15, 1997