

DEC 1 8 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 268

For corners in

<u>INGHAM COUNTY</u>	Located In:	Corner Code #
(County)		
STOCKBRIDGE TOWNSHIP		
1. Public Land Survey	T <u>1N</u> R <u>2E</u>	<u>B-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED

970044060
11/05/1997 12:39:56
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3		⊙											
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, DAVID L. CLIFFORD, in a field survey on SEPTEMBER 2, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 comers, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. JOSEPH WAMPLER D.S. SET POST FOR CORNER IN ORIGINAL GOVERNMENT SURVEY IN NOVEMBER 1825: W.O. 17" S43 1/2 W 103LKS; ASPEN 8" N44W, 79 1/2 LKS.
2. RON HELSEL, RLS 18994 USED CORNER IN AN ACT 132 SURVEY RECORDED IN LIBER 7 PAGE 101 AND RECORDED AN ACT 74 CERTIFICATES IN LIBER 8 PAGE 116 & LIBER 8 PAGE 117 IN MARCH 1994 AS A FOUND 3/4" PIPE, SET BY WOLVERINE ENGINEERS IN A SURVEY DATED JUNE 10, 1992, DESCRIBED AS SET AT N & E-W FENCE LINES: SET GALV. NAIL & TAG #18994 E/SIDE 14" ASH, SOUTH, 72.17'; FOUND NAIL & TAG #28414 E/SIDE 14" ASH, S20°W, 26.70'; SET GALV. NAIL & TAG #18994 E/SIDE 16" ASH, S25°E, 77.86'; SET GALV. NAIL & TAG #18994 S/SIDE 8" ELM, S80°E, 44.20'. R. HELSEL ALSO STATES THAT HE EXCAVATED DOWN TO A PILE OF FIELD STONES IN A LARGE CIRCLE.
3. M. MAHIEU LPS #28414 USED CORNER IN AN ACT 132 SURVEY RECORDED IN LIBER 7 PAGE 613 IN APRIL 1995 AS A FOUND 3/4" PIPE WITH SAME MONUMENT & WITNESSES AS ITEM 3

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND A 3/4" PIPE AT EAST-WEST-NORTH FENCE INTERSECTION MATCHING ALL WITNESSES FROM PART A. AFTER TRAVERSING ALL OF SECTION 6 ACCEPTED 3/4" PIPE AS PERPETUATION OF ORIGINAL CORNER BECAUSE OF AGREEMENT WITH PRORATIONAL MEASUREMENT TO ORIGINAL GOVERNMENT MEASUREMENT AND OCCUPATION. CAPPED 3/4" PIPE WITH PA 345 CAP. MEASURED EAST 2658.20' TO C-3. MEASURED WEST 2302.98' TO A-3. MEASURED NORTH 2644.88' TO B-2.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-3 T1N, R2E
3/4" STEEL PIPE & YELLOW PLASTIC CAP IMPRINTED PA 345 PS 25837 AT 3 WAY FENCE CORNER
FOUND NAIL & TAG #18994 EAST SIDE 14" ASH, 185° NAZ, 72.17'
SET NAIL & TAG #25837 WEST SIDE 28" OAK, 05° NAZ, 104.0'
FOUND NAIL & TAG #28414 EAST SIDE 14" ASH, 205° NAZ, 26.70'
FOUND NAIL & TAG #18994 EAST SIDE 16" ASH, 170° NAZ, 77.85'
FOUND NAIL & TAG #18989, SOUTH SIDE 8" DEAD ASH, 90° NAZ, 36.50'

Signed by David L. Clifford
Surveyor's Michigan License No. 25837

Date OCTOBER 14, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 26, 1971

REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1985

P.A. 345 INGHAM COUNTY
PEER APPROVED: 10/16/97 M

