

RECORD SURVEY &
 REFINANCE DIVISION
 APR 10 1995

FILED

OCT 26 11 41 AM '94

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS
Paula Johnson
 INGHAM COUNTY, MICH.

For corners in _____ Located In: _____ Corner Code # _____

INGHAM
 (County)

STOCKBRIDGE TOWNSHIP

1. Public Land Survey T 1N R 2E _____ C-1 _____
 T _____ R _____ _____
 T _____ R _____ _____
 T _____ R _____ _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1			1										
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David L. Clifford field survey on April 23, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1. Original Post set by J. Wampler DS in Nov. 1825 Intersected N. Bdy. 323 lks (213.2') W. of post Ash 13 S33E 33 Ash 17 S62W 34
 2. Corner referred to in the private records (Now in the possession of Wolverine Engineers and Surveyors) of J. Yokum former Washtenaw County Surveyor in 1878 with no mention of mon. or witnesses.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: (OVER)

Searched at apparent location of corner and found 1/2" pipe with cap #11370 at E-W-S fence corner. Excavated all around it and found nothing more. Measured the exact GLO falling (213.2') East to a post hole at C-13, T2N, R2E. Accepted 1/2" pipe as perpetuation of corner and drove Standard Ingham County Remonumentation Marker in on top of it.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Standard 3/4" X 24" Bar and PA 345 Cap PS#25837
- Nail & tag #25837 in W. side 26" Swp. Oak NAZ 27° 16.99'
 Nail & tag #25837 in NE. side 10" Hick. NAZ 300° 16.49'
 Nail & tag #18998 in N. side 8" Oak NAZ 259° 6.12'
 Nail & tag #25837 in W. side 8" Hick NAZ 158° 14.65'
 3/4" Smooth Steel Bar & PA 345 Cap PS #25837 (C-13, T2N, R2E)
 NAZ 88° 213.20'



Signed by *David Clifford* Date AUGUST 9, 1994

3. W.A. Rowe Co. Surveyor used corner in Oct. 1895 (field book 15 page 26) as "old post found" with no mention of witness
4. R. Lester LS 18998 recorded corner in June 1973 (Liber 2 page 471) and used in a survey (Liber 1 page 857) as a found $\frac{1}{2}$ " Pipe & Cap at S-E-W fence corner
Nail & tag in W. side 36" W.O. NNE 16.99'
Nail & tag in N. side 10" Hick. West 16.49'
Nail & tag in N. side 8" W.O. SW 6.09'
5. A. Williams LS #21275 used corner in a survey in Aug 1980 (Liber 4 page 138) with same mon. & wit. as in item 4
6. M. Fouty used corner in a survey in Aug 1986 (Liber 5 page 95) with same mon. & wit. as in item 4.