

SURVEY & REMONUMENTATION

FILED

LIBER 8 PAGE 274

APR 10 1995

OCT 26 11 41 AM '94

LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

INGHAM Located In: Corner Code #
STOCKBRIDGE TOWNSHIP

- 1. Public Land Survey T 1N R 2E E-3
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

REGISTER OF DEEDS
INGHAM COUNTY, MICH.
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David Clifford, in a field survey on May 30, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. Original Post set by J. Wampler DS in Nov. 1825
W. Oak 22 S86E 30
B. Oak 17 S46W 30
- 2. Corner used by A. Jackson in a survey recorded in June 1854 in Vol. 2 page 209



(OVER)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Searched at apparent location of corner and found 1/2" iron at North base of fallen down Anchor Post with all 1988 witnesses still standing. Excavated all around Anchor Post and found large amount of broken drain tile along with typical run of the mill fence post stones. Accepted 1/2" bar as perpetuation of corner and replaced it with standard bar and cap. Measured North 2667.96 feet to E-2. Measured East 2665.99 feet to F-3

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Standard Ingham County Remonumentation 3/4" Bar PA345 cap PS25837
- Set Nail & Tag #25837 in W. Side 13" Cherry NAZ 165° 14.19
- Set Nail & Tag #25837 in N. Side 8" Trip. Cherry NAZ 84° 35.14
- Set Nail & Tag #25837 in S.E. Side 36" Oak NAZ 238° 25.38
- Set Nail & Tag #25837 in N. Side 22" DbL. Oak NAZ 292° 29.95

Signed by David Clifford Date July 12, 1994

Surveyor's Michigan License No. 25837
2685

3. A. Williams LS#21275 recorded corner in Jan. 1980 in Liber 6 of Corners page 50 as a found $\frac{1}{2}$ " iron rod at N-E-W anchor post.
Nail & Tag 10" Wild Cherry S05°E 14.39'
Nail & Tag 30" Oak S45°W 25.28'
Nail & Tag 14" Wild Cherry East 25.52'
4. Corner recovered by this Surveyor during Super Collider Project Same mon. and witnesses as item 3 except they are to Nail & Tag 25837
5. M. Mahieu LS #28414 used corner in a survey in July 1989 recorded in Liber 5 of Surveys page 1136 with same mon. and witnesses as in item 4
6. R. Helsel L.S. #18994 used corner in a Survey in Oct. 1993 recorded in Liber 7 of Surveys page 29 with same mon. and witnesses as in item 4.

2685