

DEC 17 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 413

For corners in

INGHAM COUNTY Located In: Corner Code #
 (County)
 STOCKBRIDGE TOWNSHIP
 1. Public Land Survey T 1N R 2E K-2
 T ___ R ___
 T ___ R ___
 T ___ R ___
 2. Property Controlling S ___ T ___ R ___
 in Section S ___
 T ___ R ___
 3. Miscellaneous T ___ R ___
 Property in Sec. S ___ T ___ R ___

FILED

980060989
12/01/1998 09:35:56
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____ 5.
Private Claims _____

I, DAVID L. CLIFFORD, in a field survey on SEP 1, 1998 Do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 comers, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- JOSEPH WAMPLER D.S. SET POST IN ORIGINAL GOVERNMENT SURVEY IN NOVEMBER 1825; B.O. 19" S2W 38 LKS; W.O. 14" N58E 37 LKS;
- FG SEE, DEPUTY COUNTY SURVEYOR, USED CORNER IN A SURVEY RECORDED IN VOLUME 1 INGHAM COUNTY SURVEYOR RECORDS PAGE 127 IN OCT. 1844 WITH NO MENTION OF MONUMENT OR WITNESSES.
- TJ BROWN, COUNTY SURVEYOR, USED CORNER IN A SURVEY RECORDED IN VOLUME 2 INGHAM COUNTY SURVEYOR RECORDS PAGE 348 IN JUNE 1858 WITH NO MENTION OF MONUMENT OR WITNESSES.
- GARY R. BOSS RLS #17022 RECORDED CORNER IN LIBER 5 OF CORNERS PAGE 2 IN OCT. 1978 AND USED IT IN A SURVEY RECORDED IN LIBER 2 OF SURVEYS PAGE 1203 IN MAY 1977 AS A FD. T IRON; N14W N. E/S 26" HICKORY 103.24'; N47E N. NE/S 20" HICKORY 41.77'; N77E N. N/S 14" HICKORY 116.00'; S75E N. N/S 24" HICKORY 115.57'
- GEORGE YOUNG RLS # 17640 USED CORNER IN SURVEYS RECORDED IN LIBER 3 OF SURVEYS PAGE 848 IN MAY. 1973, LIBER 5 OF SURVEYS PAGE 167 IN MAY 1987, LIBER 5 OF SURVEYS PAGE 292 IN SEP. 1987, LIBER 5 OF SURVEYS PAGE 294 IN FEB. 1988 AND LIBER 5 OF SURVEYS PAGE 448 IN MAY 1988 WITH THE SAME MONUMENT AND WITNESSES AS ITEM A-4.
- MAURICE MAHIEU RLS #28414 RECORDED CORNER IN LIBER 7 OF CORNERS PAGE 269 IN JULY 1992 AND USED CORNER IN SURVEYS RECORDED IN LIBER 6 OF SURVEYS PAGES 983 AND 1250 IN JULY 1992 & JULY 1993, LIBER 7 OF SURVEYS PAGES 88 & 94 IN FEB. 1994, LIBER 7 OF SURVEYS PAGES 1102, 1127 & 1203 IN APRIL, MAY & JUNE 1997 AS A FOUND T IRON; NAIL & TAG #28414 IN SOUTH SIDE WOOD POST, N45°E, 58.46'; NAIL & TAG #28414 IN SW SIDE 32" HICKORY, S40°E, 41.30'; SOUTH SIDE OF SIGN POST, WEST, 19.95'; SW CORNER SIGN POST, N50°E, 43.09'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND A T IRON IN MONUMENT BOX RING 1' EAST OF CENTERLINE BROGAN ROAD ON CENTERLINE KINSEY ROAD TO EAST MATCHING ALL OF BOSS'S WITNESS (THE 2 HICKORY WITNESSES TO THE SE BEING STANDING BUT DEAD) AND ALL OF MAHIEU'S WITNESSES. REMOVED T IRON & MONUMENT BOX AND EXCAVATED 2' X 3' DEEP HOLE AND FOUND NO OTHER EVIDENCE OF CORNER LOCATION. ACCEPTED T IRON AS PERPETUATED LOCATION OF CORNER AND REPLACED IT WITH 3/4" BAR & ALUMINUM CAP AND RESET MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2 T1N-R2E
3/4" BAR & 2 1/2" ALUMINUM CAP STAMPED PA 345 LS 25837 INGHAM COUNTY IN MONUMENT BOX
FOUND NAIL & TAG 25832, E. SIDE 23" HICKORY, 137° NAZ, 41.30'
SET NAIL & TAG 25837, S. SIDE 19" HICKORY, 62° NAZ, 115.20'
FOUND NAIL & TAG 28414, SW SIDE 19" HICKORY (DEAD), 137° NAZ, 41.30'
SET NAIL & TAG #25837, S. SIDE 41" OAK, 69° NAZ, 169.27'
SET NAIL & TAG #25837, S. SIDE 31" OAK, 74° NAZ, 216.60'
FOUND NAIL & TAG #28414, E. SIDE DECAPITATED UTILITY POLE, 43° NAZ, 58.32'

Signed by David Clifford
Surveyor's Michigan License No. 25837

Date SEPTEMBER 19, 1998

