

DEC 17 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 416

For corners in

INGHAM COUNTY
(County)

Located in: Corner Code #

STOCKBRIDGE TOWNSHIP
1. Public Land Survey

T 1N R 2E L-2
T R
T R
T R
S T R
T R
S T R

2. Property Controlling
in Section

3. Miscellaneous
Property in Sec.

4. Lot No. _____, Recorded Plat _____ 5. Private
Claims _____

FILED

980060992
12/01/1998 09:36:01
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

I, DAVID L. CLIFFORD, in a field survey on SEP. 1, 1998 Do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 - CORNER NOT SET IN ORIGINAL GOVERNMENT SURVEY.
 - TJ BROWN, COUNTY SURVEYOR, USED CORNER IN A SURVEY RECORDED IN VOLUME 2 INGHAM COUNTY SURVEYOR RECORDS PAGE 348 IN JUNE 1858 WITH NO MENTION OF MONUMENT AND 2 WITNESSES; HICKORY 12" S83E 183-2/3 LKS (121.2'); HICKORY 14" S241/4E 221 LKS (145.9'). BROWN ALSO SHOWED CORNER TO LIE IN MIDDLE OF AN EAST-WEST ROAD ON THE WEST SIDE OF A 3 ROD ROAD RIGHT OF WAY TO THE NORTH.
 - GARY R. BOSS RLS #17022 RECORDED CORNER IN LIBER 5 OF CORNERS PAGE 1 & 2 IN OCT. 1978 AND USED IT IN SURVEYS RECORDED IN LIBER 2 OF SURVEYS PAGE 1203 IN MAY 1977, LIBER 6 OF SURVEYS PAGES 943 & 1045 IN NOV. 1991 & SEP. 1992 AS A FOUND 1/2" PIPE; S42W N. N/S 40" MAPLE 39.29'; N22W N. W/S 14" HICKORY 23.79'; N32E N. W/S 10" HICKORY 56.17'; S74E N. N/S 26" TREE 63.07'
 - GEORGE YOUNG RLS # 17640 USED CORNER IN A SURVEY RECORDED IN LIBER 4 OF SURVEYS PAGE 341 IN JULY 1981 WITH THE SAME MONUMENT & WITNESSES AS ITEM A3
 - MAURICE MAHIEU LPS #28414 RECORDED CORNER IN LIBER 7 OF CORNERS PAGE 329 IN JULY 1993 AND USED CORNER IN SURVEYS RECORDED IN LIBER 6 OF SURVEYS PAGE 1250 IN JULY 1993 AND LIBER 7 OF SURVEYS PAGE 1203 IN JUNE 1997 AS A FOUND 1/2" IRON PIPE; NAIL & TAG #28414 IN SOUTH SIDE 48" WALNUT, N80°E, 80.45'; NAIL & TAG #29238 IN SOUTH SIDE 36" MAPLE, N75°W, 57.94'; NAIL & TAG #29238 NORTH SIDE 28" WALNUT, S80°W, 79.45'; NAIL & TAG #29238 WEST SIDE 36" MAPLE N20°W 23.70'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND A 1/2" PIPE 2' NORTH OF CENTERLINE KINSEY ROAD ON WEST SIDE OF AN ABANDONED ROAD TO THE NORTH MATCHING 2 OF BOSS'S WITNESSES AND ALL OF MAHIEU'S WITNESSES. BOTH OF BROWNS HICKORY WITNESSES ARE NOW STUMPS AND MATCH LOCATION OF CORNER BY BEARING & DISTANCE. REMOVED PIPE AND EXCAVATED 2' X 3' DEEP HOLE AND FOUND NO OTHER EVIDENCE OF CORNER LOCATION. ACCEPTED 1/2" PIPE AS PERPETUATED LOCATION OF CORNER AND REPLACED IT WITH 3/4" BAR & ALUMINUM CAP AND SET MONUMENT BOX. CORNER IS 17.2' SOUTH AND 0.8' WEST OF INTERSECTION OF 1/4 LINES. MEASURED NORTH 1973.59' TO L-1, EAST 2612.61 TO M-2, SOUTH 2642.27' TO L-3 AND WEST 2608.15 TO K-2.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-2 T1N-R2E
- 3/4" BAR & 2 1/2" ALUMINUM CAP STAMPED PA 345 LS 25837 INGHAM COUNTY IN MONUMENT BOX
- FOUND BOSS ENGINEERING NAIL & TAG, NORTH SIDE 20" WALNUT, S64°W, 79.44'
- FOUND BOSS ENGINEERING NAIL & TAG, WEST SIDE 23" MAPLE, N25°W, 23.44'
- FOUND NAIL & TAG #28414, SOUTH SIDE 36" OAK, N70°E, 80.44'
- SET NAIL & TAG #25837, WEST SIDE 19" OAK, N3269° NAZ, 169.27'
- SET NAIL & TAG #25837, S. SIDE 31" OAK, 74° NAZ, 216.60'
- FOUND NAIL & TAG #28414, E. SIDE DECAPITATED UTILITY POLE, 43° NAZ, 58.32'

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by David Clifford
Michigan License No. 25837

Date SEPTEMBER 19, 1998



P.A. 345 INGHAM COUNTY
PEER APPROVED: 11/4/98 MC