

Summary  
REMONUMENTATION

DEC 12 1997

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 270

COMMISSION

For corners in

INGHAM COUNTY  
(County)

Located In: Corner Code #

WHITE OAK TOWNSHIP

1. Public Land Survey

T 2N R 2E M-13  
T \_\_\_\_\_ R \_\_\_\_\_  
T 1N R 2E M-1  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

FILED

970044062  
11/05/1997 12:39:59  
REGISTER OF DEEDS  
Paula Johnson  
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, DAVID L. CLIFFORD, in a field survey on OCTOBER 2, 1997  
Do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

M-1 T1N/R2E

A. Description of original monument and accessories and/or subsequent restoration:

1. JOSEPH WAMPLER D.S. SET POST IN ORIGINAL GOVERNMENT SURVEY IN NOVEMBER 1825; W.O. 14" S19E 107LKS; W.O. 8" S57W 97LKS
2. T.J. BROWN, COUNTY SURVEYOR, CALLED CORNER A POST IN A SURVEY RECORDED IN VOLUME 2 PAGE 329 IN JANUARY 1858
3. R. LESTER, RLS #18998, RECORDED CORNER IN LIBER 5 PAGE 237 IN APRIL 1979 AS A SET 4" X 36" CONCRETE MONUMENT WITH 1/2" X 38" REROD WITH CAP #18998. PART B OF THIS CERTIFICATE READS: EXCAVATED A HOLE 8' X 9' TO AN AVERAGE DEPTH OF 4', EAST OF THE CENTERLINE OF KANE ROAD AND ON A FENCE LINE TO THE WEST. FOUND A POINTED ROCK (4" X 20") WITH SLEIGH SHOE ALONG ITS NORTHWEST SIDE, + OR - 5.0' EAST OF THE CENTERLINE OF KANE ROAD AND ON A FENCE LINE TO THE WEST AND 4.5' NORTH OF THE FENCE LINE TO THE EAST. MEASURED NORTH + OR - 5335' TO M-11 IN CLOSE ACCORD WITH T.J. BROWN SURVEY NOTED ABOVE. ACCEPTED SLEIGH SHOE FOR CORNER. HE THEN LISTED 4 WITNESSES: NAIL & TAG #18998, NORTH SIDE 18" OAK, EAST, 212.32'; NAIL & TAG # 18998, EAST SIDE 5" RED CEDAR, SE, 28.71'; NAIL & TAG #18998, NE SIDE 6" CORNER POST, ESE, 20.95'; NAIL & TAG #18998, SW SIDE 6" WOOD GATE POST, WNW, 28.97'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND A 4" CONCRETE MONUMENT WITH 1/2" BAR & ILLEGIBLE CAP 3' EAST OF CENTERLINE KANE ROAD ON FENCE LINE TO WEST & 4.5' NORTH OF FENCE LINE TO EAST. ACCEPTED MONUMENT AS PERPETUATION OF CORNER BASED ON R. LESTER'S LCRC INFORMATION & CAPPED IT WITH PA 345 CAP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
M-13 T2N, R2E  
4" CONCRETE MONUMENT & YELLOW PLASTIC CAP IMPRINTED PA 345 PS 25837  
FOUND NAIL & TAG #18998 NORTH SIDE 19" HICKORY, 95° NAZ, 212.29'  
SET NAIL & TAG #25837 WEST SIDE 5" HICKORY, 150° NAZ, 33.18'  
FOUND NAIL & TAG #18998 NE SIDE GATE POST, 297° NAZ, 29.13'  
FOUND NAIL & TAG #28414 (M. MAHIEU) WEST SIDE 10" CEDAR, 140° NAZ, 28.35'  
FOUND NAIL & TAG #28414 SOUTH SIDE ANCHOR POST, 275° NAZ, 26.76'  
FOUND LARGE SPIKE NE SIDE GATE POST, 320°, NAZ, 39.21'  
FOUND NAIL & TAG # 28414 NORTH SIDE RAILROAD TIE ANCHOR POST, 110° NAZ, 20.85'



Signed by David L. Clifford  
Surveyor's Michigan License No. 25837

Date OCTOBER 16, 1997

P.A. 345 INGHAM COUNTY  
PEER APPROVED: 10/16/97 *W*