

DEC 17 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 418

SECTION

For corners in

INGHAM COUNTY
(County)

Located In: Corner Code #

STOCKBRIDGE TOWNSHIP
1. Public Land Survey

T 1N R 2E M-2
T R
T R
T R
S T R
S T R
S T R
S T R

2. Property Controlling in Section
3. Miscellaneous Property in Sec.

4. Lot No. , Recorded Plat
5. Private Claims

FILED

980060994
12/01/1998 09:36:05
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

I, DAVID L. CLIFFORD, in a field survey on OCTOBER 26, 1998
Do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1. JOSEPH WAMPLER D.S. SET POST IN ORIGINAL GOVERNMENT SURVEY IN NOVEMBER 1825, W.O. 13" S25°W 208 LKS; B.O. 11" N7°W 110 LKS

2. R. LESTER, RLS #18998, RECORDED CORNER IN LIBER 6 PAGE 149 IN JAN. 1981 AS A SET 4" X 38" CONCRETE MONUMENT WITH A 1/2" X 36" BAR WITH CAP # 18998 ON STANDARD LINE BETWEEN M-1 & M-3 AT A PRORATED GOVERNMENT DISTANCE NORTH OF M-3 AFTER A 10' X 14' X 3' DEEP EXCAVATION REVEALED NO EVIDENCE OF A HISTORICAL NATURE; NAIL & TAG # 18998 WEST SIDE 6" ELM, NE 50.56'; NAIL & TAG # 18998 NORTH SIDE 6" ELM, SE 37.61'; NAIL & TAG # 18998 SOUTH SIDE 12" LOCUST, WEST, 23.06'; NAIL & TAG # 18998 EAST SIDE 20" OAK, NNW, 61.63';

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
SEARCHED AT APPARENT LOCATION OF CORNER ON SEPTEMBER 17, 1998 AND FOUND A 4" CONCRETE MONUMENT WITH 1/2" BAR & CAP #18998 ON THE CENTERLINE OF KANE ROAD 7" NORTH OF A FENCE LINE TO THE WEST MATCHING 2 OF LESTER'S WITNESSES. RETURNED ON OCTOBER 26 1998 AND EXCAVATED 10' X 10' X 4' DEEP HOLE ON CENTERLINE KANE ROAD ON FENCE LINE TO WEST AND FOUND NO FURTHER INDICATION OF CORNER. ACCEPTED MONUMENT AS CORNER AND CAPPED IT WITH STANDARD INGHAM COUNTY CAP. MEASURED NORTH 1843.07' TO M-1, SOUTH 2672.21' TO M-3 AND WEST 2612.61 TO L-2.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2 T1N, R2E
4" CONCRETE MONUMENT WITH 2 1/2" ALUMINUM CAP STAMPED PA 345 INGHAM COUNTY 25837
FOUND NAIL & TAG #25832 WEST SIDE 12" ASH, N20°E, 90.05'
FOUND NAIL & TAG #25832 SE. SIDE 19" MAPLE, S45°W, 27.20'
SET NAIL & TAG #25837 NE SIDE 12" MAPLE, N55°W, 27.32'
FOUND NAIL & TAG #18998 SOUTH SIDE 17' LOCUST, N65°W, 23.05'
FOUND NAIL & TAG #18998 EAST SIDE 31" OAK, N18°W, 61.51'



Signed by David Clifford
Surveyor's Michigan License No. 25837

Date NOVEMBER 4, 1998