

DEC 17 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 419

SECTION

For corners in

INGHAM COUNTY
(County)

Located In: Corner Code #

STOCKBRIDGE TOWNSHIP

1. Public Land Survey

T 1N R 2E M-3

2. Property Controlling
in Section

S T R

3. Miscellaneous
Property in Sec.

S T R

4. Lot No. _____, Recorded Plat _____
Private Claims _____

5.

FILED

980060995
12/01/1998 09:36:06
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

I, DAVID L. CLIFFORD, in a field survey on MAY 22, 1998 Do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1. JOSEPH WAMPLER D.S. SET POST IN ORIGINAL GOVERNMENT SURVEY IN NOVEMBER 1825, W.O. 11" N26 1/2°W 91 LKS; B.O. 16" S82°W 30 LKS

2. A.P. DRAKE, COUNTY SURVEYOR, CALLED CORNER A STONE IN A SURVEY RECORDED IN VOLUME 2 PAGE 165 IN APRIL 1879; HICKORY, 8", N21 1/4°W, 118 1/2 LKS; HICKORY, 10", N87 1/4°E, 147 LKS

3. C. GARLOCK RLS #14762, RECORDED CORNER IN LIBER 1 PAGE 335 IN JAN. 1972 AND USED IT IN AN ACT 132 SURVEY RECORDED IN LIBER 1 PAGE 174 IN JAN. 1972 AS A SET 1/2" X 18" IRON ROD 192.78' NORTH OF NW CORNER SECTION 7, T1N, R3E; CENTERLINE 8" RED OAK, S20°E, 53.7'; CENTERLINE 12" LOCUST FENCE CORNER, WEST, 29.7'; CENTERLINE 8" RED OAK LEANING, N15°W, 66.55'

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
SEARCHED AT APPARENT LOCATION OF CORNER ON MAY 22 1998 AND FOUND A 1/2" REBAR ON THE CENTERLINE OF KANE ROAD ON A FENCE LINE TO THE WEST MATCHING 2 OF GARLOCK'S WITNESSES. NONE OF DRAKES WITNESSES NOW STAND. EXCAVATED 3' X 3' X 2' DEEP HOLE AND FOUND NO FURTHER INDICATION OF CORNER. RETURNED ON OCTOBER 26 1998 AND EXCAVATED 10' X 10' X 4' DEEP HOLE AND STILL FOUND NO FURTHER INDICATION OF CORNER. ACCEPTED 1/2" BAR AS PERPETUATION OF CORNER AND REPLACED IT WITH STANDARD MONUMENT. MEASURED WEST 2607.81' TO L-3 AND NORTH 2672.21 TO M-2.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3 T1N, R2E
3/4" X 24" STEEL BAR WITH 2 1/2" ALUMINUM CAP STAMPED PA 345 INGHAM COUNTY 25837
SET NAIL & TAG #25837 WEST SIDE 18" OAK, N37°E, 57.23'
SET NAIL & TAG #25837 SW. SIDE 8" WALNUT, S45°E, 35.33'
SET NAIL & TAG #25837 EAST SIDE 16" LOCUST, S44°W, 40.12'
SET NAIL & TAG #25837 SOUTH SIDE 19' LOCUST FENCE CORNER, N86°W, 29.88'
SET NAIL & TAG #25837 EAST SIDE 19" OAK, N15°W, 66.50'
SET NAIL & TAG #25837 EAST SIDE 7" LOCUST, S37°W, 34.54'



Signed by David Clifford

Date NOVEMBER 4, 1998

Surveyor's Michigan License No. 25837

P.A. 345 INGHAM COUNTY
PEER APPROVED 11/4/98 *mu*