

DEC 1 2 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 252

For corners in

INGHAM	Located In:	Corner Code #
(County)		
ONONDAGA TOWNSHIP		
1. Public Land Survey	T 1N R 2W	B-3
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous	S T R	
Property in Sec.	S T R	

FILED

970041268
10/20/1997 16:13:00
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, DAVID L. CLIFFORD, in a field survey on OCT. 07, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3	7	8	9	10	11	12						
4												
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- ORIGINAL POST SET BY HERVEY PARKE D.S. JAN. 1826.
W.O. 34" N7E 19(12.5)
W.O. 20" S62E 19(12.5)
- T. J. BROWN, CO. SURVEY USED CORNER IN SURVEY RECORDED IN VOL C. PG 4 IN NOV. 1847 WITH SAME MONUMENT AND WITNESSES AS GLO.
- A. P. DRAKE, CO. SURVEYOR USED CORNER IN SURVEY RECORDED IN VOL 3 PG 148 IN JUNE 1878 AS A STONE SET FOR CORNER
- INGHAM COUNTY ROAD COMMISSION WITNESSES CALL FOR AN IRON, STONE, BRICK
SW CORNER HOUSE NE 131.15
20" HICKORY, WNW, 124.8'
10" HICKORY, NW, 29.3'
1 1/4" IRON, S. 33.0'
- CLYDE K. STEPHENS, LS 3829 RECORDED CORNER IN LIBER 1, PAGE 325 IN DEC. 1971 AND USED IT IN AN ACT 132 SURVEY RECORDED IN LIBER 1 PAGE 138 IN NOV. 1971 AS A 1" IRON ROD
SURVEY TAG IN SOUTH SIDE 20" HICKORY N81°23'W 124.25'
SW CORNER HOUSE N55°23'E 130.75'
SURVEY TAG IN NORTH SIDE UTILITY POLE S76°49'E 103.40'
- JIM STEPHENS, RLS 16053 USED CORNER IN AN ACT 132 SURVEY RECORDED IN LIBER 1 PAGE 990 IN OCTOBER 1973 WITH NO MENTION OF MONUMENT OR WITNESSES.
- LAVERNE HENDRICKS, RLS 3276 USED CORNER IN AN ACT 132 SURVEY RECORDED IN LIBER 3 PAGE 291 IN OCTOBER 1973 WITH NO MENTION OF MONUMENT OR WITNESSES.
- AUSTIN WILLIAMS, RLS 21275, USED CORNER IN AN ACT 132 SUEVEY RECORDED IN LIBER 3 PAGE 299 IN APRIL 1978 WITH NO MENTION OF MONUMENT OR WITNESSES.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPEARENT LOCATION OF CORNER AND FOUND 1-1/4" PIPE WITH METAL CAP IN MONUMENT BOX 2' NORTH OF CENTERLINE OF FERRIS ROAD. MATCHING 2 ROAD COMMISSION WITNESSES AND 3 OF CLYDE STEPHENS WITNESSES. PROBED BOTTOM OF BOX AND HIT STONE. ACCEPTED 1-1/4" PIPE AS PERPETUATION OF CORNER AND STAMPED LS25837 IN TOP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-3 T1N R2W
- 1-1/4" PIPE WITH METAL CAP STAMPED 25837 IN MONUMENT BOX, 2' NORTH OF CENTERLINE FERRIS RD. ON FENCE LINE TO SOUTH.
- SET NAIL AND TAG # 28409 IN SOUTH SIDE 30" SHAGBARK HICKORY, 282° NAZ, 124.75'
- SET NAIL AND TAG # 28409 IN NORTH SIDE TWIN 8" BUTTERNUT, 255° NAZ, 82.80'
- FOUND NAIL AND TAG # 16053 IN NORTH WEST SIDE POWER POLE, 107° NAZ., 103.47'
- SET NAIL AND TAG # 28409 IN NORTH EAST SIDE OF 5" HICKORY 314° NAZ., 30.25'
- SOUTHWEST CORNER FOUNDATION HOUSE, 60° NAZ., 130.35'

Signed by David L. Clifford

Date JUNE 2, 1997

Surveyor's Michigan License No. 25837

