

DEC 1 10 05 AM '94

REGISTER OF DEEDS
INGHAM COUNTY, MICH.

SURVEY & REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners of INGHAM (County) Located in: _____ Corner Code 44

- ONONDAGA TOWNSHIP COMMISSION**
1. Public Land Survey T 1N R 2W _____ K-10
 T _____ R _____
 T _____ R _____
 T _____ R _____
2. Property Controlling S _____ T _____ R _____
 In Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, RONALD L. ENGER in a field survey on SEPTEMBER 16, 1994
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	D	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1. ORIGINAL POST SET BY HERVEY PARKE, DEPUTY SURVEYOR, ON DEC. 25, 1825.
 ELM 18 NORTH 58 (38.3')
 MAPLE S69E 22 (14.5')
2. A MARGINAL NOTE IN THE INGHAM COUNTY REGISTER OF DEEDS' COPY OF GLO NOTES NEW
 W.O. 12 N13-5/6W 112 (73.9')

B. CONTINUED ON BACK
Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND 1" PIPE AND CAP AS RECORDED BY ME IN JANUARY 1989. INVESTIGATION OF AREA SHOWS THAT THIS PIPE IS ACTUALLY AT VERY OLD INTERSECTION OF OCCUPATION LINES AND WILLIAMS IRON IS AT INTERSECTION OF A PILE OF GARBAGE. TIED OCCUPATION AT 1/16 CORNER 1/4 MILE SOUTH AND COMPARED IT TO LOCATION OF 1/4 CORNER 1/2 MILE SOUTH AND FOUND THAT IT AGREES WITH POSITION OF 1" PIPE AS CORNER. ACCEPTED 1" PIPE AS POSITION OF CORNER BECAUSE OF ITS AGREEMENT WITH ADJACENT OCCUPATION AND BECAUSE OF ITS POSITION 1/2 WAY BETWEEN ADJACENT SECTION CORNERS. MEASURED NORTH 2628.06' TO K-9. MEASURED SOUTH 2628.06' TO K-11. MEASURED WEST 2639.59 TO J-10. MEASUREMENTS ARE FROM TRAVERSE DURING THE SUPER COLLIDER PROJECT OF 1988.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-10 T1N R2W
 1" IRON PIPE AND PA 345 CAP PS 28409
 NAIL & TAG 28414 IN NORTH SIDE MULTIPLE 6" MAPLE, NAZ 47°, 9.38'
 NAIL & TAG 28414 (M. MAHIEU) IN WEST SIDE 6" MAPLE, NAZ 328°, 12.08'
 NAIL & TAG 18998 (R. LESTER) IN EAST SIDE 13" MAPLE, NAZ 206°, 5.83'
 NAIL & TAG 28414 IN N.E. SIDE TWIN 6" MAPLE, NAZ 137°, 18.56'
 1/2" IRON (RECORDED LIBER 5 PAGE 279 AS CORNER), NAZ 176°, 14.85'



Signed by Ronald L. Enger Date NOVEMBER 1, 1994

Surveyor's Michigan License No. 28409

2761

K-10 T1N R2W
PART A CONTINUED

3. A. JACKSON, CO. SURVEYOR, USED CORNER IN OCTOBER 1839 (VOL 1, PAGE 18) WITH SAME MON. AND WITNESSES AS ITEM 1.

4. A. JACKSON, CO. SURVEYOR, USED CORNER IN NOV. 1852 (VOL. 2, PAGE 124) WITH THE SAME MONUMENT AND WITNESSES AS ITEM 1 AND 3.

5. E.A. CALKINS SHOWS WITNESS TO CORNER (FOLDER #1, PAGE 1) FROM NEW NOTES ON ORIGINAL NOTES SAME AS ITEM #2.

6. A. WILLIAMS, LS 21265, RECORDED CORNER (LIBER 5 OF CORNERS, PAGE 279) AND USED IN A SURVEY (LIBER 3 OF SURVEYS, PAGE 961) IN AUGUST 1979 --"SET $\frac{1}{2}$ " IRON AND CAP BY PROPORTIONATE MEASUREMENT BETWEEN THE NW CORNER AND THE SW CORNER OF SECTION 25, T1N, R2W. POINT FALLS IN INTERSECTION OF EAST, WEST & NORTH FENCE LINES."
NAIL AND TAG 6" DBL MAPLE EAST 11.40'
NAIL AND TAG 8" MAPLE WEST 10.70'
NAIL AND TAG 6" ELM S5°W 7.60'

7. RON ENGER, LS 28409, RECORDED CORNER IN JANUARY 1989 (LIBER 7 OF CORNERS, PAGE 104) AS A SET 1"X 3' PIPE WITH CAP IN DISAGREEMENT WITH A. WILLIAMS. WILLIAMS' CORNER IS NOT MIDWAY AND ON LINE AS HIS SURVEY AND LCRC STATE. ENGER REESTABLISHED CORNER POINT MIDWAY AND ON LINE.

" BAR (WILLIAMS' MARKER), 176° NAZ, 14.85'
NAIL AND TAG E. SIDE 13" MAPLE, 206° NAZ, 5.79'
NAIL AND TAG SW SIDE 6" MAPLE, 328° NAZ, 11.93'
NAIL AND TAG SW SIDE 6" TWIN MAPLE, 137° NAZ, 19.0'
NAIL AND TAG E. SIDE OF 12" ELM, 178° NAZ, 22.29'

8. BRUCE ANTCLIFF, LS 25826, USED CORNER IN NOVEMBER 1988 (LIBER 5 OF SURVEYS, PAGES 944-947) WITH SAME MONUMENT AND WITNESSES AS ITEM 7.

9. J. GRANGER, LS 16041, USED CORNER IN A SURVEY IN JANUARY, 1994 (LIBER 7 OF SURVEYS, PAGE 82) WITH REFERENCE TO LIBER 7 OF CORNERS, PAGE 104.