

A. (CONTINUED)

4. LCRC recorded in Liber 6, Page 78 by Ronnie M. Lester PS #18998 on August 25, 1980. "Excavated a 6' x 24' hole to an average depth of 1.0' on the centerline of Kelly road and on fence line east. Found no evidence of monumentation. Corner considered lost. Set corner midway between A-13 & A-11 on standard Township line or Meridian. Measures North to A-11 2621.56'; measures South to A-13 2621.56'; measures North to M-11 Vevay 1386.16'; measured South to M-12 Vevay 1262.59'. Corner falls in centerline Kelly Road and ±5.0' North of fence line East. Witnesses to set 4" x 36" concrete monument with 1/2" x 38" rebar and cap #18998; Nail and Tag #18998 Southwest side 12" Cherry East-South-East 20.06'; Nail and Tag #18998 West side 24" Ash South-South-East 42.91'; Nail and Tag #18998 Southeast side 14" Hickory Southwest 41.58'; Nail and Tag #18998 Northeast side 12" Hickory, North-North-West 49.48."

STATE OF OHIO
DEPARTMENT OF REVENUE

DEC 17 1988

SECTION

Rcpt No	97035
CAHR	9.00
MSSR	2.00
Total	11.00

99