

OCT 13 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SEP 28 8 19 AM '93

REGISTER OF DEEDS
David Johnson
INGHAM COUNTY, MICH.

For corners in

INGHAM
(County)

Located in:

Corner Code #

INGHAM TOWNSHIP

- 1. Public Land Survey T 2N R 1E C-8
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, DAVID R. LOHR, in a field survey on JUNE 1, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
C-8

- 1. POST SET BY JOSEPH WAMPLER, DEPUTY SURVEYOR, IN 1826, WITNESSED BY 16" WHITE OAK, NORTH 18° WEST, 13 1/2 LINKS; 17" WHITE OAK, SOUTH 56 1/2° WEST, 9 LINKS.
- 2. SAME POST AND WITNESSES USED BY A. JACKSON, COUNTY SURVEYOR, 1841, VOL. 1, PAGE 139.
- 3. NO OTHER REFERENCES FOUND IN COUNTY SURVEYOR'S RECORDS.

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-8 CORNER SET BY ACCEPTABLE METHOD BY GARY LESTER IN 1971. CORNER HAS BEEN USED BY AREA SURVEYORS SINCE THAT DATE. NO EVIDENCE FOUND TO CONTRADICT LOCATION OF CORNER AS FOUND.

FOUND T-BAR IN MONUMENT BOX IN MERIDIAN ROAD AS RECORDED BY MAURICE H. MAHIEU (PS #28414) ON LIBER 7, PAGE 304. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION ON THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-8
LEFT T-BAR IN MONUMENT BOX IN MERIDIAN ROAD
WITNESSES BY:

- FOUND NAIL AND TAG #28414, NORTH SIDE OF WOOD POST, Az. 92°, 28.31'
- FOUND NAIL AND TAG #28414, NORTH SIDE OF 10" OAK, Az. 122°, 31.10'
- FOUND NAIL AND TAG #28414, NORTH SIDE OF 10" BOXELDER, Az. 134°, 34.40'
- FOUND NAIL AND TAG #28414, SOUTH SIDE OF 17" BOXELDER, Az. 65°, 31.85'

Signed by David R. Lohr

Date AUG. 24, 1993.

Surveyor's Michigan License No. 30090

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN. 28, 1988 REVISED MAY 14, 1990 REVISED JAN 28, 1993



filed 10/13/93
2486

P.A. 345 INGHAM COUNTY
PEER APPROVED 9/1/93 RL

PART A CONTINUED

C-8

4. NO REFERENCES MADE ON MERIDIAN ROAD CONSTRUCTION PLANS OF 1992.

5. INGHAM COUNTY ROAD COMMISSION, MERIDIAN ROAD FIELD NOTES DATED AUGUST 18, 1959, SHOW BOATSPIKE AT STA. 26+59.0, WITNESSED BY SPIKE IN 14" ELM, WNW, 34.30', SPIKE IN 12" ELM, NORTHEAST, 36.30', SPIKE IN 42" OAK, SSE, 41.80'. THIS LOCATION DOES NOT FIT CORNER LOCATION, DOES NOT APPEAR TO BE SAME POINT. DISTANCES NORTH AND SOUTH DO NOT AGREE WITH ANY RECORDED DISTANCES.

6. CORNER RE-SET BY SINGLE PROPORTIONATE MEASURE BY GARY LESTER (PS #17624), JUNE 16, 1971 AS RECORDED IN LIBER 1, PAGE 71. "SET T-BAR AND CAP IN MERIDIAN ROAD AT INTERSECTION OF FENCE LINE TO EAST." WITNESSED BY:

NAIL AND TAG IN 24" CHERRY, NORTHWEST 175.14'
 NAIL AND TAG IN 18" STUPM, NORTHEAST, 121.13'
 NAIL AND TAG IN FENCE CORNER POST, EAST 29.83'

7. INGHAM COUNTY REMON SQUAD ON NOVEMBER 15, 1978, "FOUND T-BAR AS PER LIBER 1, PAGE 71. T-BAR WAS ACCEPTED AS CORNER." WITNESSED BY:

NAIL AND TAG SOUTH SIDE OF 4" MAPLE, SOUTH 30° EAST, 31.30'
 RLS NAIL AND TAG #17640 (GEORGE YOUNG) WEST SIDE OF TWIN MULBERRY, NORTH 35° EAST, 56.90'
 P.K. NAIL, 1' WEST OF CENTERLINE, SOUTH 18.70'

8. CORNER REFERRED TO IN UNRECORDED SURVEY BY GEORGE YOUNG ON MARCH 16, 1987 "WILLIAMS/KOVACH" AS "FOUND T-BAR IN BOX". EXACT SAME WITNESSES AS LIBER 1, PAGE 71.

9. CORNER REFERRED TO IN SURVEY BY MAURICE H. MAHIEU ON DECEMBER 6, 1991, RECORDED IN LIBER 6, PAGE 921. "FOUND T-BAR IN MONUMENT BOX". WITNESSED BY:

NAIL AND TAG #28414 NORTH SIDE OF WOOD POST, EAST, 28.25'
 NAIL AND TAG #28414 SOUTH SIDE OF 24" BOXELDER, NORTH 70° EAST, 31.85'
 NAIL AND TAG #28414 NORTH SIDE OF 12" OAK, SOUTH 70° EAST, 31.13'
 NAIL AND TAG #28414 NORTH SIDE OF 12" BOXELDER, SOUTH 50° EAST, 34.40'

10. CORNER RECORDED BY MAURICE H. MAHIEU IN LIBER 7, PAGE 304, SEPTEMBER 23, 1992. "FOUND T-BAR IN MONUMENT BOX IN MERIDIAN ROAD AS PER LIBER 1, PAGE 71." WITNESSED BY:

NAIL AND TAG #28414, NORTH SIDE OF WOOD POST, EAST, 28.25'
 NAIL AND TAG #28414 NORTH SIDE OF 15" OAK, SOUTH 70° EAST, 31.10'
 NAIL AND TAG #28414, NORTH SIDE OF 15" BOXELDER, SOUTH 50° EAST, 34.40'
 NAIL AND TAG #28414, SOUTH SIDE OF 28" BOXELDER, NORTH 75° EAST, 31.85'

11. PRIVATE SURVEYOR'S RECORDS REVEAL NO ADDITIONAL DATA.