

SURVEY &
REMONUMENTATION

LIBER 7 PAGE 347
FILED

OCT 13 1993

SEP 28 8 19 AM '93

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MICH.

For corners in

INGHAM
(County)
INGHAM TOWNSHIP

Located In: Corner Code #

1. Public Land Survey T 2N R 1E C-9
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, DAVID R. LOHR, in a field survey on JUNE 1, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-9
1. POST SET BY JOSEPH WAMPLER, DEPUTY SURVEYOR IN 1826. WITNESSED BY 18" ASPEN, SOUTH 76° WEST 31 LINKS, 12" B. OAK, NORTH 41° EAST 36 LINKS.
 2. SURVEY BY A. JACKSON 1846, VOL. 1, PAGE 184 USES SAME WITNESSES.
 3. T-BAR AND CAP SET IN MERIDIAN ROAD BY GARY LESTER ON JUNE 24, 1971 IN LIBER 1, PAGE 73. "OLD FENCE LINE TO EAST SUPPORTED BY MEASUREMENTS NORTH AND SOUTH TO EVIDENCE OF OTHER OBLITERATED GOVERNMENT CORNERS AND DEEDED DIMENSIONS TO OCCUPATION LINES WESTERLY OF CORNER, CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-9 CORNER SET BY GARY LESTER IN 1971. CORNER HAS BEEN USED BY AREA SURVEYORS SINCE THAT DATE. NO EVIDENCE FOUND TO CONTRADICT LOCATION OF CORNER AS FOUND.

FOUND T-BAR IN MONUMENT BOX IN CENTERLINE OF MERIDIAN ROAD AS RECORDED BY MAURICE H. MAHIEU, LIBER 7, PAGE 303, SEPTEMBER 23, 1992. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9 LEFT T-BAR IN MONUMENT BOX IN THE CENTERLINE OF MERIDIAN ROAD 28' NORTH OF THE CENTERLINE OF DEXTER TRAIL.

FOUND NAIL AND TAG #28414 WEST SIDE OF UTILITY POLE	Az. 13°50', 104.32'
FOUND NAIL AND TAG #28414 NE SIDE OF UTILITY POLE	Az. 329°06', 66.76'
SOUTHWEST CORNER GARAGE FOUNDATION WALL	Az. 107°28', 75.23'
FOUND NAIL AND TAG #28414 EAST SIDE OF 20" MAPLE	Az. 202°20', 110.77'
FOUND NAIL AND TAG #17624 EAST SIDE OF UTILITY POLE	Az. 331°04', 54.84'
FOUND NAIL AND TAG NORTHWEST SIDE OF FENCE POST	Az. 59°22', 31.85'

Signed by David R. Lohr Date AUG. 24, 1993
Surveyor's Michigan License No. 30090

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS
STATE OF MICHIGAN
DAVID R. LOHR
PROFESSIONAL SURVEYOR
LICENSED PROFESSIONAL SURVEYOR
NO. 30090

P.A. 345 INGHAM COUNTY
PEER APPROVED 9/1/93 RL

filed 10/13/93
D.R.L.

PART A CONTINUED

C-9

3. AND WITNESSED BY:"

NAIL AND TAG IN FENCE CORNER POST ENE, 30.70'
 NAIL AND TAG IN POWER POLE NW, 54.61'
 NAIL AND TAG IN 24" MAPLE TREE SW, 63.97'

4. INGHAM COUNTY REMON SQUAD ON APRIL 12, 1978, "FOUND T-BAR ON FENCE LINE TO EAST AS PER LIBER 1, PAGE 73." INGHAM COUNTY REMON WITNESSES OF 1978:
 FOUND RLS TAG ON EAST SIDE OF POWER POLE, RLS #17624 (GARY LESTER) NORTH 30° WEST, 54.61'
 FOUND RLS TAG #17624 NORTH SIDE OF 6" WOOD FENCE POST, NORTH 55° EAST, 30.98'
 SET NAIL AND TAG ON NORTHWEST SIDE OF 48" MAPLE, SOUTH 65° WEST, 83.07'
 FOUND 2 P.K. NAILS ON PHY CENTERLINE OF DEXTER AND MERIDIAN ROADS, DUE SOUTH, 14.00'

5. CORNER REFERENCED TO BY GEORGE YOUNG, LS #17640, ON JULY 10, 1980 IN SURVEY RECORDED IN LIBER 4, PAGE 104. EXACT SAME WITNESSES AS PER LIBER 1, PAGE 73. SEE ITEM #3.

6. CORNER RECORDED BY MAURICE H. MAHIEU IN LIBER 7, PAGE 303, SEPTEMBER 23, 1992 WITNESSED BY:

NAIL AND TAG #28414, WEST SIDE OF UTILITY POLE	N 10° E, 104.32'
NAIL AND TAG #28414, NORTHEAST SIDE OF UTILITY POLE	N 34° W, 66.76'
SOUTHWEST CORNER OF GARAGE FOUNDATION WALL	S 80° E, 75.23'
NAIL AND TAG #28414, EAST SIDE OF 20" MAPLE	S 30° W, 110.77'

"FOUND "T" BAR IN MONUMENT BOX IN THE CENTERLINE OF MERIDIAN ROAD."

7. PRIVATE SURVEYOR'S RECORDS REVEAL NO ADDITIONAL DATA.