

DEC 17 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 348

For corners in INGHAM TOWNSHIP

INGHAM COUNTY	Located In:	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>1E</u>	<u>C-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED

980049408
09/29/1998 10:51:47
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Maurice H. Mahieu, in a field survey on July 27, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. Original corner set by Joseph Wampler D.S. during February, 1826 at a distance of 80.00 chains. "Set P Cor. 29, 30, 31 & 32 FW; RO 16 N 42 W 18; DW 9 S 54 W 21".
2. Additional notes to Joseph Wampler's (different handwriting) show the following witnesses: " Hick 5 N 77 1/2 E 48; Hick 5 S 68 1/2 E 74 1/2".
3. Road Commission map shows a sleigh shoe as monumentation with the following witnesses: 12" Hickory N 78° E 32.4'; 8" Hickory W 37.2'; 12" Hickory SE 131.8'.

(Continued On Back)

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron ±1' West of East edge asphalt on Meridian road & on fenceline to West, occupation to East. No witnesses found. Excavated a 2' x 2' x 4' area. Encountered a 1" plastic utility conduit running N-S at about 3 feet deep. Found nothing else. Area is considerably higher than surrounding landscape. Original monumentation believed to be obliterated during road construction. Replaced 1/2" iron with 3/4" iron & PA 345 aluminum cap #28414 and constructed monument box around. Accepted location of 1/2" iron as perpetuated position of corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1/2" iron and replaced with 3/4" iron and aluminum P.A. 345 cap #28414 and constructed monument box around.

Witnessed by:

- Set Nail and Tag #28414 West side 4" White Pine S 40° E 58.07'
- Set Nail and Tag #28414 South side 10" Walnut S 80° W 69.68'
- Set Nail and Tag #28414 North side Sextuple Basswood N 85° W 48.94'
- Set Nail and Tag #28414 West side 6" Hickory S 20° E 138.73'

Signed by Maurice H. Mahieu Date 9-17-98

Surveyor's Michigan License No. 28414



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 26, 1971
REVISED MAY 14, 1975

REVISED JAN., 1983
REVISED OCT., 1985

P.A. 345 INGHAM COUNTY
PEER APPROVED 8/11/98 *W*

A. (CONTINUED)

- 4. LCRC recorded in Liber 3, Page 614 by George M. Young RLS #17640 on August 10, 1976. Set 1/2" steel rod & cap on prorated distance between S 1/4 post Sec. 29 & West line Sec. 30 & on prorated existing line fences (E-W 1/4 line Sec. 32, S. sec. line Sec. 29) & NW Corner. Sec. 29 (Found Iron). Witnesses: P.K. Nail in 15" Ash S 85° W 57.40'; #10 Nail in 8" Walnut S 50° W 69.52'; #10 Nail in 12" Ash S 85° E 23.64'; Traveled centerline Meridian Road W 10±.
- 5. P.A. 132 survey recorded in Liber 2, Page 1091 on April 29, 1977 by George M. Young RLS #17640. No monumentation or witnesses listed. Measured 2628.09' to D-11 & 2627.92' to C-12.
- 6. P.A. 132 survey recorded in Liber 5, Page 172 on April 1, 1987 by Ronnie M. Lester PS #18998 Monumentation same as #5. Witnesses: Nail and Tag in South side 15" Elm, East 23.72'; Nail and Tag in South side 12" Elm, SE 26.85'; Nail and Tag in West side Power Pole, SSE 164.43'; Nail and Tag in South side 21" Oak W.S.W. 104.16'. Measured 2623.00' to D-11 & 2627.64' to C-12.
- 7. P.A. 132 survey recorded in Liber 5, Page 227 on June 11, 1987 by Ronnie M. Lester PS #18998 Monumentation & Witnesses same as in #7, as are measurements to D-11 & C-12.

SURVEY &
REMONUMENTATION

DEC 17 1998

SECTION

Rep't No	97035
CRHR	9.00
HSSR	2.00
Total	11.00