

NOV 04 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

OCT 26 8 28 AM '93

REGISTER OF DEEDS Paul Johnson INGHAM COUNTY, MICH.

For corners in

Table with columns: Ingham (County), Ingham Township, Located In, Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, DAVID R. LOHR, in a field survey on OCTOBER 6, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13. A circled '9' is located at row 9, column E.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: E-9

- 1. POST SET BY JOSEPH WAMPLER, DEPUTY SURVEYOR, 1826. WITNESSED BY: WHITE OAK 16" SOUTH 23 1/2 WEST, 29 LINKS. B. OAK 18" SOUTH 67 EAST, 30 LINKS.

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: E-9

FOUND 5/8" REBAR AS PER ITEMS 5 AND 6. AREA IS IN PINETREE PLANTATION AND NO EVIDENCE OF OCCUPATION LINES ARE VISIBLE.

NO EVIDENCE OF PREVIOUS POST OR WITNESSES WERE FOUND DUE TO PRESUMED CLEARING OF LAND FOR TREE PLANTATION. ACCEPTED 5/8" REBAR AS CORNER BECAUSE OF ACCEPTED USAGE AND NO PHYSICAL EVIDENCE TO DISPUTE ITS LOCATION.

LEFT 5/8" REBAR IN PLACE AND ADDED PA 345 CAP #30090.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: E-9

- 5/8" X 34" REBAR WITH PA 345 CAP #30090. WITNESSED BY: SET GALV. NAIL AND TAG #30090, N/ROOT 20" MAPLE EAST 25.20' FOUND P.K. NAIL E/S 10" PINE SOUTH 14.20' SET GALV. NAIL AND TAG #30090 N/S 10" PINE S 85 W, 21.80' SET GALV. NAIL AND TAG #30090 SW/S 14" POPLAR N 54 W, 23.90' FD. NAIL AND TAG #17640 E/S 10" DEAD POPLAR N 27 W, 20.00' SET GALV. NAIL AND TAG #30090, W/S 6" MAPLE N 12 W, 31.00'

Signed by David R. Lohr Date OCTOBER 13, 1993 Surveyor's Michigan License No. 30090



FORM APPROVED BY MICHIGAN STATE SURVEYORS, INC. 21 1984 REVISED MAY 1975

P.A. 345 INGHAM COUNTY PEER APPROVED: 10/21/93

2518 11-5-93

PART A CONTINUED
E-9

2. SAME POST AND WITNESSES USED BY A. JACKSON, COUNTY SURVEYOR, 1848, RECORDED IN VOLUME 1, PAGE 259, INGHAM COUNTY SURVEYORS RECORDS.
3. SURVEY BY DAVID HOLES, DEPUTY SURVEYOR, 1855, VOLUME 1, PAGE 321, SHOWS POST WITNESSED BY:
 - MAPLE 10" NORTH 54 EAST, 7 1/2 LINKS
 - MAPLE 8" SOUTH 24 WEST, 22 LINKS
 - WHITE OAK 18" NORTH 26 EAST, 45 LINKS
 - WHITE OAK 20" NORTH 67 1/2 WEST, 67 LINKS
4. ADDITIONAL SURVEYS BY A. JACKSON USING ORIGINAL WITNESSES OF 1826:
 - 1848, VOLUME 2, PAGE 97
 - 1848, VOLUME 2, PAGE 98
 - 1849, FOLDER 1, PAGE 63
 - 1855, FOLDER 1, PAGE 46
5. CORNER SET BY GEORGE YOUNG, P.S. #17640, ON FEBRUARY 17, 1987, RECORDED IN LIBER 6, PAGE 311 (LCRC). "CORNER COMMON TO FOUR SECTIONS RESTORED BY DOUBLE PROPORTIONATE MEASURE. SET #5 IRON REBAR." WITNESSED BY:
 - NAIL AND TAG WEST SIDE 20" MAPLE, EAST, 25.20'
 - NAIL AND TAG EAST SIDE 10" POPLAR, NORTH, 19.95'
 - NAIL AND TAG EAST SIDE 12" PINE, SOUTH, 14.15'
6. CORNER USED IN UNRECORDED SURVEY BY GEORGE YOUNG, P.S. #17640. SURVEY IS DATED MARCH 16, 1987, AND TITLED "WILLIAMS/KOVACH". SURVEY SHOWS SAME WITNESSES AS IN ITEM #5 ABOVE BUT ALSO SHOWS DISTANCE NORTH TO BE 2630.01' AND DISTANCE EAST TO BE 2615.03'. REVIEW OF FIELD TRAVERSE NOTES AND COMPUTATIONS ALSO SHOWS THE DISTANCE SOUTH TO BE 2621.23' AND THE DISTANCE WEST TO BE 2648.81'.