

NOV 04 1993

OCT 26 8 29 AM '93

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich: P.A. 1970

For corners in

REGISTER OF DEEDS David Johnson INGHAM COUNTY, MICH.

Form with fields for Ingham County, Township, Public Land Survey, Property Controlling, Miscellaneous, Lot No., and Private Claims.

Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 2-13, containing numbers 1-36 and a circled '9' at row 9, column F.

I, DAVID R. LOHR, in a field survey on OCTOBER 6, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: F-9

1. POST SET BY JOSEPH WAMPLER, DEPUTY SURVEYOR, 1826. WITNESSED BY: BEECH 5" NORTH 49° WEST, 7 1/2 LINKS ELM 11" SOUTH 57° EAST, 23 LINKS

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: F-9

FOUND 1/2" IRON (NO CAP) IN FARM LANE, 5' SOUTH OF CENTER OF LANE. MEASURED NORTH TO VERIFY IRON AS THAT OF GEORGE YOUNG AS PER "WILLIAMS/KOVACH" SURVEY (ITEMS 7 AND 8). FOUND WILLIAMS IRON (ITEMS 5 AND 6) TO BE SOUTH 30° 41' WEST, 24.00'.

IGNORED WILLIAMS IRON DUE TO IMPROPER METHOD USED TO SET IT (DOUBLE PROPORTIONATE MEASURE).

ACCEPTED GEO. YOUNG IRON WHICH WAS SET BY SINGLE PROPORTIONATE MEASURE.

REPLACED 1/2" IRON WITH STANDARD 3/4" X 24" BAR AND CAP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: F-9

SET STANDARD 3/4" X 24" INGHAM COUNTY REMONUMENTATION BAR AND PA 345 CAP #30090 IN FARM LANE. WITNESSED BY:

- SET GALV. NAIL/TAG #30090 IN SE/S 26" HICKORY Az. 183 40', 319.38'
SET GALV. NAIL/TAG #30090 IN SE/S 28" HICKORY Az. 185 54', 237.82
SET GALV. NAIL/TAG #30090 IN N/S 28" HICKORY Az. 254 40', 433.32'
SET GALV. NAIL/TAG #30090 IN N/S 30" ASH Az. 271 00', 727.41'
SET GALV. NAIL/TAG #30090 IN S/S 18" TW. MAPLE Az. 285 00', 737.74'


Signed by David R. Lohr

Date OCTOBER 13, 1993

Surveyor's Michigan License No. 30090

2519 11-5-93

P.A. 345 INGHAM COUNTY PEER APPROVED 10/21/93 R



## PART A CONTINUED

2. SAME ORIGINAL WITNESSED USED IN FOLLOWING:  
SURVEY BY A. JACKSON, 1849, FOLDER 1, PAGE 63.  
SURVEY BY A. JACKSON, DATE UNKNOWN, VOLUME 2, PAGE 98.  
SURVEY BY D. HOLMES, 1853, VOLUME 2, PAGE 165.
3. SURVEY BY DAVID HOLMES, DEPUTY SURVEYOR, 1855, VOLUME 1, PAGE 321, SHOWS POST WITNESSED BY:  
ELM 12" SOUTH 10 1/4 EAST, 24 LINKS  
LYNN 5" NORTH 17 WEST, 25 1/2 LINKS
4. NO OTHER REFERENCES FOUND IN COUNTY SURVEYOR RECORDS.
5. CORNER SET BY AUSTIN C. WILLIAMS, PS #21275, ON MARCH 24, 1977, RECORDED IN LCRC LIBER 4, PAGE 285. "SET 1/2 IRON BAR WITH CAP BY PROPORTIONATE MEASUREMENT AT NORTH-SOUTH-EAST AND WEST. WITNESSED BY:  
1/2" IRON BAR WITH CAP, NORTH 33.00'  
1/2" IRON BAR WITH CAP, WEST 33.00'  
1/2" IRON BAR WITH CAP, SOUTH 33.00'
6. SURVEY BY A. WILLIAMS, RECORDED IN LIBER 2, PAGE 1062, DATED MARCH 27, 1977, SHOWS DISTANCE TO EAST AS 2628.5'
7. CORNER SET BY GEORGE YOUNG, PS #17640, ON FEBRUARY 17, 1987, RECORDED IN LCRC LIBER 6, PAGE 312. "AREA IS OPEN FIELD. NO EVIDENCE OF CORNER OR ACCESSORIES WERE FOUND. CORNER RESET MIDWAY BETWEEN E-9 AND G-9, 2615.03 FEET EACH WAY. SET 1/2" IRON AND CAP AT CORNER LOCATION."  
WITNESSED BY:  
IRON, NORTH 00 52'32" WEST 656.98 FEET,  
CORNER ON NORTH AND SOUTH LINE (1/4 LINE);  
BEARING OF SOUTH LINE IS NORTH 89 42'18" EAST  
(SECTION LINE EAST)
8. CORNER USED IN UNRECORDED SURVEY BY GEORGE YOUNG AND TITLED "WILLIAMS/KOVACH," DATED MARCH 16, 1987. SURVEY SHOWS DISTANCE EAST AND WEST TO BE 2615.03'. SAME WITNESSES AS IN ITEM 7 ABOVE.