

OCT 13 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SEP 28 8 18 AM '93

For corners in

INGHAM (County) INGHAM TOWNSHIP

Located In:

Corner Code #

- 1. Public Land Survey T 2N R 1E G-8
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

REGISTER OF DEEDS Frank J. Johnson INGHAM COUNTY, MICH.

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 2-13. Cell G-8 contains a circled cross symbol.

I, DAVID R. LOHR, in a field survey on JUNE 1, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-8 1. POST SET BY JOSEPH WAMPLER, DEPUTY SURVEYOR, 1826. WITNESSED BY 7" ASH, SOUTH 82° WEST, 10 LINKS, 9" ELM, NORTH 24° WEST 18 LINKS.
2. SAME POST AND WITNESSES USED BY A. JACKSON, COUNTY SURVEYOR, 1841, RECORDED IN VOL. 1, PAGE 141 AND IN 1848, VOL. 1, PAGE 154, INGHAM COUNTY SURVEYOR'S RECORDS.
3. SAME POST AND WITNESSES USED BY DAVID HOMES, DEPUTY SURVEYOR, 1848, VOL. 1, PAGE 259, INGHAM COUNTY SURVEYOR'S RECORDS.

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-8 FOUND 1/2" IRON IN MONUMENT BOX AS RECORDED IN LIBER 6, PAGE 92. THIS CORNER WAS RE-ESTABLISHED AS PART OF THE PREVIOUS REMON PROGRAM IN 1980, AND IT'S LOCATION IS ACCEPTED AS THAT OF G-8.

THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-8 LEFT MONUMENT IN MONUMENT BOX, WITNESSED BY:
FOUND NAIL AND TAG #18998, SOUTH SIDE OF 15" MAPLE Az. 98°, 36.86'
FOUND NAIL AND TAG #18998, SOUTH SIDE OF FENCE POST, Az. 314°, 34.97'
SET NAIL AND TAG #30090, SOUTH SIDE OF MULTI 8" MAPLE Az. 59°, 26.75'
FOUND NAIL AND TAG #18998, SOUTH SIDE OF TRI 14" MAPLE Az. 35°, 31.61'
SET NAIL AND TAG #30090, SOUTHEAST SIDE OF 12" MAPLE Az. 240°, 50.42'
SET NAIL AND TAG #30090, SOUTHEAST SIDE OF 26" MAPLE Az. 213°, 72.48'

Signed by David R. Lohr Date AUGUST 24, 1993
Surveyor's Michigan License No. 30090



filed 10/13/93 2481

PART A CONTINUED

G-8

4. OTHER SURVEYS BY JACKSON USING SAME ORIGINAL WITNESSES RECORDED IN:

1841, VOL. 1, PAGE 146
1848, VOL. 1, PAGE 162
1848, VOL. 2, PAGE 97
1848, FOLDER 1, PAGE 46
1841, FOLDER 1, PAGE 48

5. NO OTHER REFERENCES FOUND IN COUNTY SURVEYOR'S RECORDS.

6. CORNER SET BY RONNIE LESTER, INGHAM COUNTY REMON PROGRAM, JULY 2, 1980, LIBER 6, PAGE 92, SET 1/2" IRON IN 4" CONCRETE MONUMENT MIDWAY ON LINE BETWEEN G-7 AND G-9 (SINGLE PROPORTIONATE MEASURE).

WITNESSED BY:

NAIL AND TAG #18998, SOUTH SIDE OF 10" MAPLE EAST, 36.70'
NAIL AND TAG #18998, SOUTH SIDE OF FENCE POST, NORTHWEST 34.22'
NAIL AND TAG #18998, SOUTH SIDE OF MULTI 8" MAPLE, NORTHEAST, 26.65'
NAIL AND TAG #18998, SOUTH SIDE OF TRI 8" MAPLE, NORTHEAST 31.77'

"NO EXCAVATION WAS CONDUCTED AT THIS LOCATION BECAUSE OF LOCATION AND EXCESSIVE DEPTH."

INVESTIGATION AND RESEARCH CONDUCTED BY INGHAM COUNTY SURVEY AND REMONUMENTATION PROJECT STAFF, 1980

7. CORNER REFERENCED BY A. WILLIAMS, LS #21275 ON APRIL 23, 1980, RECORDED IN LIBER 3, PAGE 1274. NO MENTION OF MONUMENT, HOWEVER, WITNESSES ARE EXACTLY THE SAME AS ON LIBER 6, PAGE 92 OF JULY 2, 1980.

8. CORNER REFERENCED IN UNRECORDED SURVEY "WILLIAMS/KOVACH" BY GEORGE YOUNG, LS #17640 ON MARCH 16, 1987. "SET 4" X 36" MONUMENT ... DESCRIBED ABOVE" THIS STATEMENT AND WITNESSES ARE VERBATIM FROM LIBER 6, PAGE 92.