

DEC 17 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 360

For corners in

INGHAM

Located In:

Corner Code #

(County)

INGHAM TOWNSHIP

1. Public Land Survey

T2N R 1E L-9

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

FILED

980053098
10/19/1998 13:54:52
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, David R. Lohr, in a field survey on 6/10, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-9: "SET QR. P (POST) AT AV D FW" BY J. WAMPLER, DEPUTY SURVEYOR IN FEBRUARY 1826.
WITNESSED BY: WHITE OAK 14" - N87°E - 44 LINKS - (29.04')
" 18" - N35°E - 53 LINKS - (34.98')
NOTES SHOW DISTANCE EAST & WEST OF 39.50 CHAINS (2607.00')
(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9: SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND 1/2" IRON/CAP #18998 AS PER LCRC OF LIBER 4, PAGE 12. FOUND RON LESTERS WITNESS TREE TO NORTH AND P. POLE TO EAST. ACCEPTED 1/2" IRON AS FAITHFUL PERPETUATION OF CORNER. REMOVED 1/2" IRON, AND REPLACED WITH STANDARD 3/4" X 24" REMON. BAR & 2" ALUMINUM P.A. 345 CAP STAMPED #30090. DID NOT EXCAVATE CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9: SET 3/4" X 24" STANDARD REMON BAR WITH 2" ALUMINUM CAP STAMPED #30090 ALONG THE EAST SIDE 10" POST, WITNESSED BY:
FD. N&T #18998, N/S P. POLE - EAST - 3.45'
FD. N&T #18998, W/S 6" THORNAPPLE, SSE 6.75'
SET N&T #30090 S/S 6" OAK - SW -13.40'
FD. N&T #18998 W/S 15" CHERRY - NORTH - 30.50'



Signed by David R. Lohr
Surveyor's Michigan License No. 30090

Date 9-24-98

P.A. 345 INGHAM COUNTY
PEER APPROVED 8/11/98 M

DEC 17 1998

Liber 9 Page 361

SECTION

L-9:PART A, CONTINUED.

- 2) CORNER REFERENCED IN COUNTY SURVEYOR RECORDS, BOOK 4, PAGE 132(OLD VOL. 1, PAGE 135) BY ANSON JACKSON, COUNTY SURVEYOR, DATED NOV. 23, 1838. NO REFERENCE TO MONUMENT. WITNESSED BY SAME WITNESSES AS ITEM A-1 ABOVE. SURVEY SHOWS DISTANCE WEST OF 155 R 22LKS (2571.02')
SURVEY SHOWS DISTANCE SOUTH OF 156 R 46 LKS (2604.36')
- 3) CORNER REFERENCE IN COUNTY RECORDS BOOK 4, PAGE 135 (OLD VOL1, PAGE 159) BY ANSON JACKSON, COUNTY SURVEYOR, DATED FEB: 6&7, 1839. NO REFERENCE TO MONUMENT; WITNESSED BY: ASPEN 11", S 73 1/2 E, 81 LKS (53.46')
ASPEN 10", N 79 E, 86 LKS (56.76')
- 4) CORNER REFERENCED IN COUNTY SURVEYOR RECORDS BOOK 4, PAGE 295 (OLD VOLUME 2, PAGE 137) BY A. JACKSON, COUNTY SURVEYOR, DATED FEBRUARY 7, 1853. NO REFERENCE TO CORNER. WITNESSED BY:
SURVEY SHOWS DISTANCE SOUTH TO L-10 OF 157 RODS, 21 LINKS, (2604.36')
- 5) CORNER NOT REFERENCED ON INGHAM COUNTY ROAD COMMISSION SECTION CORNER MAP DATED JANUARY 1969.
- 6) CORNER REFERENCED ON SURVEY BY RON LESTER #18998, RECORDED IN LIBER 2, PAGE 1014, DATED NOVEMBER 24, 1976. "1/2" BAR & CAP" WITNESSED BY:
NAIL & TAG EAST SIDE 12" CHERRY - NORTH - 30.44'
NAIL & TAG NORTH SIDE POWER POLE. - EAST - 3.60'
BASE OF GUY WIRE, NNE, 21.50'
SURVEY SHOWS DISTANCE EAST TO L-10 OF 2588.24'
- 7) LCRC BY RON LESTER DATED DECEMBER 21, 1976 RECORDED IN LIBER 4, PAGE 12 STATES: SET 1/2" BAR & CAP AT BASE OF OLD FENCE POST WITH STONES, AT BASE OF OLD FENCE ROW NORTH AND OLD FENCE FENCE ROW EAST & WEST, DISTANCE EAST 2588.24'. WITNESSES AS ITEM #7 ABOVE.
- 8) NO OTHER REFERENCED FOUND.