

DEC 17 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 356

For corners in:

<u>INGHAM</u>	Located In:	Corner Code #
(County)		
INGHAM TOWNSHIP		
1. Public Land Survey	T <u>2N</u> R <u>1E</u>	<u>M-9</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

FILED

980053096
10/19/1998 13:54:47
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, David R. Lohr, in a field survey on 6/10, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-9: 1) "POST" SET BY J. WAMPLER, DEPUTY SURVEYOR IN FEBRUARY 1826.
WITNESSED BY: ASH 16" - N26°W - 52 LINKS - (34.32')
HY (HICKORY) 8" - S84°W - 62 LINKS - (40.92')
NOTES SHOW DISTANCE NORTH & SOUTH OF 40 CHAINS (2640.00')
NOTES SHOW DISTANCE WEST OF 39.50 CHAINS (2607.00')
(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND 1/2" REBAR & CAP#18998 AT SOUTH SIDE OF OLD ANCHOR POST REMAINS. EXCAVATED AREA AROUND ANCHOR POST AND FOUND POINTED STONE (15"long X 8" X 10") ALONG EAST SIDE OF 1/2" IRON. DID NOT EXCAVATE BEYOND STONE. FOUND RON LESTERS WITNESS TREE TO NNW. ACCEPTED 1/2" IRON AS FAITHFUL PERPETUATION OF CORNER. REMOVED 1/2" IRON, AND REPLACED WITH STANDARD 3/4" X 24" REMON. BAR & 2" ALUMINUM CAP STAMPED #30090.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9: SET 3/4" X 24" STANDARD REMON BAR/CAP #30090 SOUTH SIDE ANCHOR POST WEST OF POINTED STONE: WITNESSED BY:
FD. N&T #11370, N/S 15" WALNUT - S40°E - 35.37'
SET N&T #30090 W/S 12" WALNUT - S03°W - 60.85'
SET N&T #30090 E/S 6" WALNUT - N71°W - 41.40'
FD. N&T #11370 E/S 30" WALNUT - N17°W - 10.55'
A-9 WHITE OAK (3/4" X 24" REMON.) - SOUTH - 21.78'



Signed by David R. Lohr
Surveyor's Michigan License No. 30090

Date 9-24-98

P.A. 345 INGHAM COUNTY
PEER APPROVED: 8/11/98 *ML*

DEC 17 1998

Liber 9 Page 357

SECTION

M-9:PART A, CONTINUED.

- 2) CORNER REFERENCED IN COUNTY SURVEYOR RECORDS BOOK 4, PAGE 295 (OLD VOLUME 2, PAGE 137) BY A. JACKSON, COUNTY SURVEYOR, DATED FEBRUARY 7, 1853. NO REFERENCE TO CORNER. WITNESSED BY:
ASH 16" - N26°W - 52 LINKS (34.32')
HICKORY 8" - S84°W - 62 LINKS (40.92')
"NO OTHER TREES"
SURVEY SHOWS DISTANCE SOUTH TO M-10 OF 158 RODS, 28 LINKS, (2635.18')
- 3) CORNER NOT REFERENCED ON INGHAM COUNTY ROAD COMMISSION SECTION CORNER MAP DATED JANUARY 1969.
- 4) CORNER REFERENCED ON SURVEY BY RON LESTER #18998, RECORDED IN LIBER 2, PAGE 1014, DATED NOVEMBER 24, 1976. NO REFERENCE TO MONUMENT.
WITNESSED BY: NAIL & TAG#18998 WEST SIDE 24" WALNUT - NNW - 10.47'
NAIL & TAG#18998 NORTH EAST SIDE 6"CH. - SSE - 26.26'
1/2" BAR & CAP NW CORNER SECTION 30, T2N, R2E SOUTH 21.78,
SHOWS DISTANCE SOUTH TO M-10 OF 2623.97'
SHOWS DISTANCE WEST TO L-9 OF 2588.24'
- 5) LCRC BY RON LESTER DATED DECEMBER 21, 1976 RECORDED IN LIBER 4, PAGE 12 STATES: SET 1/2" BAR & CAP ON TOWNLINE ON OLD FENCE LINE WEST. FALLS 1.5' WEST OF OLD FENCE TO NORTH. WITNESSES AS ITEM #4 ABOVE.
- 6) NO OTHER REFERENCES FOUND.

FILED