

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

INGHAM
(County)
INGHAM TOWNSHIP
1. Public Land Survey

Located In:	Corner Code #
T <u>2N</u> R <u>1E</u>	<u>M-11</u>
T ___ R ___	_____
T ___ R ___	_____
T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____

FILED

RECORDED
970029264
08/06/1997 09:00:03
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DAVID R. LOHR, in a field survey on 3/25, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-11: 1. CORNER SET BY JOSEPH WAMPLER IN FEB. 1824. (EXTERIOR BOUNDARY - INGHAM TOWNSHIP) "SET POST COR 25 & 36 - FW" WITNESSED BY:
"A" (ASPEN) 14 N 46 W 540 LKS (356.4')
"A" (ASPEN) 17 S 14 W 200 LKS (132.0')
NOTES SHOW DISTANCES NORTH & SOUTH OF 40 CH. (2640.0')

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11: SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND 1/2" BAR AND CAP #18998 AS PER ITEM #6, PART A: CORNER FALLS 4.7 FT. NORTH OF FENCE TO EAST AND ON CENTERLINE OF MEECH ROAD. FOUND ALL WITNESSES OF ITEM #A-6. DID NOT EXCAVATE DUE TO CORNER FALLING IN 6 FT. FILL AREA AND A LACK OF ANY COUNTY SURVEYOR RECORDS FOR THIS CORNER. ACCEPTED CORNER BASED ON TESTIMONY OF SURVEYOR LESTER IN ITEM #A-6. REPLACED 1/2" IRON WITH STANDARD 3/4" X 24" REMON. BAR AND PA#345 CAP #30090.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11: STANDARD 3/4" X 24" REMON. BAR AND PA#345 CAP #30090 IN CENTERLINE OF MEECH ROAD AND 4.7 FT. NORTH OF FENCE TO EAST. WITNESSED BY:
C/L 8" ST. GATE POST (NORTHERLY) AZ. 71-53-30, 80.33'
C/L 8" ST. GATE POST (SOUTHERLY) AZ. 83-19-00, 76.67'
SET N&T #30090 N/S 12" ELM, AZ. 109-29-30, 42.33'
SET N&T #30090 W/S 15" CHERRY, AZ. 165-22-00, 82.33'
FD. 3/4" PIPE, A-11 WHITE OAK, AZ. 180-00-00, 4.62'
FD. N&T #18998 NE/S 20" WALNUT, AZ. 249-36-00, 25.72'
FD. N&T #18998 NE/S 20" OAK, AZ. 287-49-30, 33.57'

Signed by David R. Lohr
Surveyor's Michigan License No. 30090

Date 6-16-97



