

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>29</u> T. <u>2</u> N. <u>1</u> E.	<u>2</u> R. <u>1</u> E.	D-10, E-10
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ N. S., R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Ingham Co

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on April, 1985, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p>D-10 Found Anchor Post East 5.00 Plat Mon. North 5.00 Plat Mon. Set: 4" x 36" Conc. mon. w/alum. cap in place of anchor post</p>	<p>E-10 Found: 3/4 Iron with cap Nail & Washer in 12" Walnut N. 19.42' Nail & Washer in 14" Pine W. 49.34' Nail & Washer in 12" Maple SW. 21.95' Set: 4" x 36" Conc. mon. with alum. cap. Flush with surface</p>
---	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>D-10 Conc. mon. w/alum. cap S74°W. 9.89' 10" Cherry S20°E 30.23' 14" R. Oak S48°E 8.01' 6" Cherry N86°E 17.59' 8" Cherry All Trees have spike & Blaze.</p>	<p>E-10 Cong. mon. w/alum. cap N58°E. 26.52' 6" Spruce S46°W. 21.95' 14" Maple S88°W. 49.34' 15" Spruce N03°W. 19.42' 16" Walnut All trees have spikes & washers</p>
---	--

SIGNED BY _____ DATE _____


SURVEYOR'S MICHIGAN REGISTRATION NO. 18655

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell DATE 5/6/85
CHIEF OF BUREAU PART 1
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. 18655

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTERED LAND SURVEYORS, 1971
REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET