

OCT 2 1 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

OCT 13 9 11 AM '93

REGISTER OF DEEDS  
*Paul Johnson*  
INGHAM COUNTY, MICH.

For corners in  
INGHAM

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 2N R 1W F-6
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, RON HELSEL in a field survey on SEPT. 30, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	

A. Description of original monument and accessories and/or subsequent restoration:

CORNER NOT SET IN ORIGINAL GOVERNMENT SURVEY.

A. JACKSON, COUNTY SURVEYOR, WITNESSED THE CORNER AS,

BEECH, 18, N77°W, 30 LINKS

BEECH 12, N18°E, 27 LINKS

IN SURVEY DATED NOV. 28, 1833, AS RECORDED IN VOLUME 1 PAGE 169 OF SURVEYS. NO DESCRIPTION OF THE MARKER WAS GIVEN.

A. JACKSON IN A SURVEY DATED NOV. 19, 1856, AS RECORDED IN VOLUME 2, PAGE 127 OF SURVEYS, WITNESSED THE CORNER AS:

SUGAR 18, N75°W, 17 3/4 LINKS

BEECH 6, S51°W, 40 LINKS

(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

THE LOCATION OF THIS CORNER LIES IN A GRAVEL PIT, SINCE ALL EVIDENCE OF THE CORNER HAS BEEN LOST, ACCEPTED YOUNG'S METHOD OF INTERSECTING THE 1/4 LINES TO ESTABLISH THE CORNER. TRAVERSED THE 1/4 CORNERS (ERROR OF CLOSURE 1/38,616) & SET 3/4" x 24" FORM PIN WITH CAP LABELED P.A. 345. WITH NO PHYSICAL WITNESSES AVAILABLE, SET 1/2" x 18" BARS WITH CAP LABELED ACCOLADE SURVEYING #18994 100.00 FEET IN EACH CARDINAL DIRECTION ALONG THE 1/4 LINES. FROM THE RECORDED SURVEYS BY YOUNG, THE FOLLOWING RELATIONSHIP WAS DETERMINED:

F-6 TO F-5 MEAS. 2642.88' (YOUNG 2641.84')

F-6 TO F-7 MEAS. 2653.03' (YOUNG 2654.07')

F-6 TO G-6 MEAS. 2641.95' (YOUNG 2643.14')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" x 24" FORM PIN SET AT INTERSECTION OF EAST-WEST & NORTH-SOUTH 1/4 LINES.

REF. BARS & CAPS #18994 SET 100.00' IN EACH CARDINAL DIRECTION ON 1/4 LINE.

F-6 TO F-5 2642.88'

F-6 TO F-7 2653.03'

F-6 TO G-6 2641.95'

F-6 TO E-6 2635.94'



Signed by Ron Helsel

Date Oct 4, 1993

Surveyor's Michigan License No. 18994

10/21/93 gm  
2493

"A" CONTINUED

FROM THE SAME PAGE, CO. SURVEYOR W.A. ROWE PERPETUATED THE CORNER AS A PLOW COULTER & TILE SET FROM JACKSON'S SUGAR AND REWITNESSED.  
APPLE 12, N-E, 59 1/2 LINKS  
BUTTERNUT 8, S45°E, 1 1/2 LINKS

SURVEYS WERE RECORDED IN LIBER 2, PGS 762 & 763  
LIBER 2, PGS 810 & 811 &  
LIBER 2, PGS 893-896

ALL WERE FIELD DATED 4-30-76 BY G.M. YOUNG #17640.  
WITNESSED AS SET 1/2" RE-ROD WITH CAP AT INT. OF THE E-W & N-S 1/4 LINES  
NAIL & WASHER IN 8" POPLAR, N40°W, 109.17'  
NAIL & WASHER IN 30" MAPLE, S20°W, 97.68'  
NAIL & WASHER IN 24" BOXELDER, SOUTH, 44.98'

A SUBSEQUENT SURVEY BY YOUNG, RECORDED IN LIBER 2, PG. 812, FIELD DATED 6-5-76, AND  
A C.R.C. FIELD DATED 6-23-76 & RECORDED IN LIBER 3, PG. 616 WERE WITNESSED:

1/2" RE-ROD WITH CAP  
NAIL & WASHER IN 8" POPLAR, N40°W, 109.17'  
NAIL & WASHER IN 24" BOXELDER, SOUTH, 44.98'  
NAIL & WASHER IN 30" MAPLE, S20°W, 97.68'

COULD NOT FIND FURTHER MENTION OF THIS CORNER IN PUBLIC RECORDS.

