

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

INGHAM

(County)

VEVAY TOWNSHIP

Located in:

Corner Code #

- 1. Public Land Survey T 2N R 1W K-8
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

FILED

11/20/1995 09:36:59
REGISTER OF DEEDS
PAULA JOHNSON
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Cell (8, 24) contains a black dot.

RONALD L. ENGER, in a field survey on OCTOBER 11, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. POST SET IN ORIGINAL GOVERNMENT SURVEY BY HERVEY PARKE, DEPUTY SURVEYOR IN FEBRUARY 1826 AND TWO BEARING TREES RECORDED: ELM 14" N70E 24 THORN 9" S70°W 6 1/2

CONTINUED ON BACK



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND OLD NORTH-SOUTH FENCE BURIED 2' DEEP IN BLACK MUCK IN DRY MILL POND (DAM FAILED IN 1981). TRAVERSED SECTION LINE AND SEARCHED AT SPLIT. FOUND EAST-WEST FENCE BURIED 2' DEEP IN DRY MILL POND. FOUND INTERSECTION OF FENCES AND FOUND 2' LONG DEPOSIT OF RUST LAYING ON GROUND. EXCAVATED AND FOUND REMAINS OF LARGE DIAMETER PIPE NEXT TO POINTED STONE (BOTTOM IS 12" DIAMETER, COMES TO ROUNDED POINT AT TOP X 18" HIGH). ACCEPTED STONE AS CORNER AND SET 3/4" X 24" SMOOTH STEEL BAR IN 3/4" X 36" GALVANIZED PIPE IN ITS PLACE AND SET STONE ON NORTH SIDE. MEASURED NORTH 2650.88 TO K-7. MEASURED SOUTH 2652.55 TO K-9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 T2N R1W
3/4" DIAMETER X 24" LONG SMOOTH STEEL BAR IN 3/4" DIAMETER X 3' LONG GALVANIZED PIPE ALONGSIDE STONE AT BURIED FENCE CORNER.
SET 20D GALVANIZED SPIKE AND TAG PS 28409 IN NORTH SIDE OF 10" TAMARACK, 249° NAZ., 151.84'
SET 20D GALVANIZED SPIKE AND TAG PS 28409 IN WEST SIDE OF 10" POPLAR, 21° NAZ., 32.90'
SET 20D GALVANIZED SPIKE AND TAG PS 28409 IN NORTH SIDE OF 8" MAPLE, 53° NAZ., 138.22'
SET 20D GALVANIZED SPIKE AND TAG PS 28409 IN SOUTH SIDE OF 14" POPLAR, 62° NAZ., 68.93'
CENTERLINE OF CREEK EAST 45'

Signed by [Signature]

OCTOBER 20, 1995 Date

Surveyor's Michigan License No.

P.A. 345 INGHAM COUNTY
PEER APPROVED 11/02/95

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

K-8 T2N RLW  
PART A CONTINUED

2. A. JACKSON, COUNTY SURVEYOR, USED CORNER IN SURVEYS IN JUNE 1839 AND JULY 1842 RECORDED IN VOLUME 1, PAGE 28 AND VOLUME 1, PAGE 39 OF COUNTY SURVEY RECORDS WITH THE SAME MONUMENTS AND WITNESSES AS PART A #1.

3. E.A. CALKINS COUNTY SURVEYOR, SET "48" X 2 1/2" LENGTH" THROUGH MILL POND ICE IN MARCH 1905 RECORDED IN FIELD BOOK 5, PAGE 145.

4. W. L. PADISON, PS. 7256, DEPARTMENT OF CONSERVATION SURVEYOR, USED FENCE POST STICKING THROUGH MILL POND ICE AS CORNER IN FEBRUARY 1961.

[Faint, mostly illegible text, possibly bleed-through from the reverse side of the page]

[Faint, mostly illegible text, possibly bleed-through from the reverse side of the page]

[Faint, mostly illegible text, possibly bleed-through from the reverse side of the page]

SEARCHED  
SERIALIZED  
INDEXED  
FILED