



DEC 17 1998

A. (CONTINUED) SECTION

6. COUNTY SURVEYOR A. JACKSON IN L3, P1245 NOTES CHERRY 17 N 12E 40; MAPLE 10 N 84 ½ E 21; NOVEMBER 7, 1856.
7. LCRC RECORDED IN LIBER 3, PAGE 393 BY FRED WHITE P.S. #12034, IN JUNE 22, 1975 "FOUND ANCHOR POST ON LINE WITH FENCE EAST, SOUTH AND TREE ROW TO NORTH. SET ½" IRON BAR AT BASE OF WEST SIDE OF ANCHOR POST. CORNER IN ACCORD WITH G.L.O. DISTANCES. WITNESSES: NAIL & TAG 12" ASH, N 70° E 63.33'; NAIL AND TAG 8" TWIN POPLAR S 55° W 28.76'; NAIL AND TAG 10" WILD CHERRY N 45° W 51.65'.
8. AN ACT 132 SURVEY RECORDED IN LIBER 2, PAGE 366 ON JUNE 22, 1975 BY FRED WHITE PS #12034 MONUMENTATION AND WITNESSES SAME AS A-7.
9. AN ACT 132 SURVEY RECORDED IN LIBER 2, PAGE 999 ON JUNE 22, 1977 BY FRED WHITE PS #12034 MONUMENTATION AND WITNESSES SAME AS A-7.
10. AN ACT 132 SURVEY RECORDED IN LIBER 4, PAGE 231 ON FEBRUARY 27, 1981 BY FRED WHITE PS #12034 MONUMENTATION AND WITNESSES SAME AS A-7.
11. AN ACT 132 SURVEY RECORDED IN LIBER 4, PAGE 234 ON FEBRUARY 27, 1981 BY FRED WHITE PS #12034 MONUMENTATION AND WITNESSES SAME AS A-7.
12. AN ACT 132 SURVEY RECORDED IN LIBER 5, PAGE 47 ON SEPTEMBER 26, 1986 BY GEORGE YOUNG PS #17640. FOUND ANCHOR POST WITNESSES SAME AS A-7.
13. AN ACT 132 SURVEY RECORDED IN LIBER 5, PAGE 123 ON DECEMBER 12, 1986 BY RONNIE LESTER PS #18998. NO MONUMENTATION GIVEN. NAIL AND TAG 3" TWIN COTTONWOOD, SW 28.38'; NAIL AND TAG 10" CHERRY, NW, 50.95'; NAIL AND TAG 10" CHERRY, SE 10.15'; NAIL AND TAG 15" ASH, NE 63.56'; MEASURED 5301.02 TO I-12, 2653.21 TO K-11.
14. AN ACT 132 SURVEY RE-RECORDED IN LIBER 5, PAGE 1238 ON DECEMBER 11, 1989 BY MAURICE MAHIEU PS #28414. MONUMENTATION AND WITNESSES SAME AS A-12. MEASURED 5299.23 TO M-12.
15. AN ACT 132 SURVEY RE-RECORDED IN LIBER 6, PAGE 669 ON NOVEMBER 19, 1990 BY MAURICE MAHIEU PS #28414. MONUMENTATION AND WITNESSES SAME AS A-12. MEASURED 5299.23 TO M-12.
16. AN UNRECORDED SURVEY ON JUNE 16, 1994 BY LARRY BRYAN PS 25832 FOUND 1" BAR AT FENCE INTERSECTION, FENCES EAST-WEST AND SOUTH. FOUND NAIL & TAG SOUTH SIDE 24" ASH, N 70° E 63.33; FOUND NAIL & TAG NORTHEAST SIDE 10" CHERRY N 45° W 51.65'; FOUND NAIL & TAG EAST SIDE TWIN 12" POLAR S 55° W 28.76'; FOUND NAIL & TAG NORTH SIDE 10" CHERRY, S 75° E 10.17'. MEASURED 2653.25 TO K-11.
17. AN ACT 132 SURVEY RECORDED IN LIBER 7, PAGE 387 ON NOVEMBER 15, 1994 BY RON HELSEL, P.S. #18994 FOUND 1" BAR IN EAST-WEST FENCE LINE & FENCE TO SOUTH. FOUND NAIL AND TAG #18998 IN SOUTH SIDE OF 10" CHERRY, S85°E 9.90'; FOUND NAIL AND TAG #17640 IN SOUTH SIDE OF 10" CHERRY, S85°E, 10.15'; FOUND NAIL AND TAG #18998 IN EAST SIDE OF 10" TWIN POPLAR, S40°W 28.76'; SET NAIL AND TAG #18998 IN WEST SIDE OF 12" QUAD. ELM, SOUTH 22.07'; SET NAIL AND TAG #18998 IN EAST SIDE OF 6" CHERRY, N10°W, 21.84'.

Rept. No	97035
CRIM	9.00
MSSR	2.00
Total	11.00