

DEC 1 2 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Liber

9 Page

286

For corners in  
VEVAY TOWNSHIP  
INGHAM COUNTY

Located in:

Corner Code #

1. Public Land Survey

T 2N R 1W

K-13

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Maurice H. Mahieu, in a field survey on September 23, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. ORIGINAL GLO CORNER WAS SET BY JOHN MULLETT, D.S. IN MAY 1825 "80.00 SET POST COR. OF SECT. 35 & 36 FW B OAK 16 N86 1/2E 50; W. OAK 18 N19W 22"

2. COUNTY SURVEYOR A. JACKSON ON SEPT 6, 1845 SURVEYED THE SW 1/4 OF SECTION 36 AS NOTED IN BOOK 1, PAGE 92. NO MENTION OF CORNER MONUMENTATION. WITNESSES SAME AS A-1 WITH AN ADDITION OF HACK 8, S45W 64 (DRAKE).

3. COUNTY SURVEYOR A. JACKSON ON NOVEMBER, 1856 NOTES "HACK 8 S45W 64" THIS INFORMATION IS FROM 1980 REMON PROGRAM DOSSIER.

(SEE BACK FOR CONTINUANCE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON FENCE POST CENTERLINE OF PLAINS ROAD. FOUND WITNESSES: NAIL & TAG #28414, WEST SIDE DOUBLE 10" WALNUT, N50°E, 48.33'; NAIL & TAG #28414, NORTH SIDE 10" HICKORY, S65°W 33.75' (TREE DEAD); NAIL & TAG #28414, EAST SIDE 15" WALNUT N30°W, 40.89'. OTHER WITNESSES OBLITERATED. EXCAVATED FENCE 2'x2'x2.5' DEEP HOLE SURROUNDING FENCE POST. FOUND NO EVIDENCE OF ANY HISTORICAL MARKER OTHER THAN FENCE POST. OBSERVATION OF THE RELATIVE ELEVATION OF EXCAVATION AREA AND SURROUNDING LANDSCAPE SHOWED EVIDENCE OF PRIOR CUT AND SUBSEQUENT FILL ACTIVITIES. THEREFORE NO FURTHER EXCAVATION WAS PERFORMED. REPLACED FENCE POST WITH 3/4" IRON ROD AND CAP STAMPED "PA 345 PS 28414" AND SET MONUMENT BOX AND COVER OVER IT. THERE WAS NO OTHER EVIDENCE IN THE AREA TO SUGGEST A DIFFERENT POSITION FOR THIS CORNER AND THEREFORE ACCEPTED THE POSITION OF THE FENCE POST AS THE PERPETUATED LOCATION FOR THIS CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" x 24" IRON ROD WITH CAP STAMPED "PA345 PS28414" IN LOCATION OF FOUND FENCE POST. WITNESSED BY:

NAIL & TAG #28414, WEST SIDE DOUBLE 10" WALNUT, N50°E 48.32 FEET

NAIL & TAG #28414, EAST SIDE 15" WALNUT, N30°W, 40.83 FEET

NAIL & TAG #28414, NORTH SIDE POWER POLE, S60°E, 105.94 FEET

NAIL & TAG #28414, EAST SIDE 18" WALNUT, S58°W, 73.97 FEET

Found 1/2" rod in monument box (A-13, Leslie Twp.) N 85° W 73.15 feet

Signed by Maurice H. Mahieu

Date 10-10-97

Surveyor's Michigan License No. 28414

FILED

970047751  
12/02/1997 13:38:27  
REGISTER OF DEEDS  
Paula Johnson  
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JUL 24, 1971  
REVISED MAY 14, 1975

REVISED JAN, 1993  
REVISED OCT, 1999

P.A. 345 INGHAM COUNTY  
PEER APPROVED 9/29/97 M

K-13 VEVAY TWP.  
PAGE 2

## SECTION A CONTINUED:

4. LCRC IN LIBER 2, PAGE 321 RECORDED ON FEB. 6, 1973, BY RICHARD W. STEADMAN, P.S. #11370. "OPPOSITE FENCE LINE NORTH, FOUND STEEL FENCE POST "T" CROSS SECTION JUST BELOW ROAD SURFACE. LEFT ABOVE MONUMENTATION IN PLACE AND TOOK THE FOLLOWING WITNESSES:  
NAIL & TAG IN SOUTHERLY TRUNK OF TWIN 12" OAK, NNE 39.38 FT.  
NAIL & TAG IN 8" WALNUT; NW, 41.10 FT.  
NAIL & TAG IN 48" OAK; WNW 84.11 FT."
5. AN ACT 132 SURVEY WAS RECORDED IN LIBER 1, PAGE 606 ON FEB. 8, 1973 BY RICHARD W. STEADMAN, P.S. #11370. MONUMENTATION AND WITNESSES SAME AS A-4
6. AN ACT 132 SURVEY WAS RECORDED IN LIBER 3, PAGE 475 ON AUG 16, 1978 BY AUSTIN WILLIAMS, P.S. #21275. NO MONUMENTATION WAS GIVEN. THE WITNESSES SAME AS A-4
7. AN ACT 132 SURVEY WAS RECORDED IN LIBER 3, PAGE 1073 ON NOV. 7, 1979 BY AUSTIN WILLIAMS, P.S. #21275. NO MONUMENTATION WAS GIVEN. THE WITNESSES SAME AS A-4.
8. AN ACT 132 SURVEY WAS RECORDED IN LIBER 5, PAGE 48 ON SEPT. 26, 1986 BY GEORGE YOUNG, P.S.#17640. MONUMENTATION AND WITNESSES SAME AS A-4.
9. AN ACT 132 SURVEY WAS RECORDED IN LIBER 5, PAGE 1179 ON OCT 18, 1989 BY RON HELSEL, P.S. #18994. ONLY REFERENCE TO CORNER WAS LIBER AND PAGE AS A-4.
10. AN ACT 132 SURVEY WAS RECORDED IN LIBER 5. Page 1242 and rerecorded in Liber 6, Page 673 on Dec. 11, 1989 and Mar 8, 1991 by this surveyor. Monumentation and witnesses for this corner same as A-4.
11. AN ACT 132 SURVEY WAS RECORDED IN LIBER 6, PAGE 323 ON AUG 9, 1990 BY THIS SURVEYOR. MONUMENTATION AND WITNESSES FOR THIS CORNER SAME AS A-4.
12. AN ACT 132 SURVEY WAS RECORDED LIBER 6, PAGE 548 ON NOV. 28, 1990 BY RON HELSEL, P.S. # 18994."FOUND "T" FENCE POST; WITNESSED BY: SET NAIL AND TAG, TWIN 16" OAK, N5°E, 39.00'  
FOUND NAIL & TAG, 10" WALNUT, N45°W 41.10'  
SET NAIL & TAG, 8" WALNUT, N45°E, 48.62'  
FOUND BAR AND CAP, NORTH, 33.00"
13. AN ACT 132 SURVEY WAS RECORDED IN LIBER 6, PAGE 1246 ON JULY 9, 1993 BY THIS SURVEYOR. "FOUND "T" BAR, WITNESSED BY:  
N & T #28414 N. SIDE 10" HICKORY S65°W, 33.75'  
N & T #28414 E. SIDE 15" WALNUT, N30°W, 40.89'  
N & T #28414 E. SIDE 12" CHERRY, N10°E, 32.97'  
N & T #28414 W. SIDE (2) 10" WALNUT, N50°W, 48.33'
14. AN ACT 132 SURVEY WAS RECORDED IN LIBER 7, PAGE 786 ON MAY 10, 1996 BY RONNIE M. LESTER P.S. #18998. \* SOUTHWEST CORNER SECTION 36, T2N, R1W, VEVAY TWP. L2, PAGE 321. T BAR. CONCRETE MONUMENT AT K-1 LESLIE MAG. AZ. 278°, 73.06'; FOUND NAIL AND TAG #28414 WEST SIDE DOUBLE 10" WALNUT MAG. AZ. 57°, 48.42'; FOUND NAIL AND TAG #28414 NORTH SIDE 10 SI LAGBARK MAG. AZ. 243°, 33.78'; FOUND NAIL AND TAG #28414 N.E. SIDE 12" WALNUT MAG. AZ. 332°, 40.89"