

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970


For corners in INGHAM County VEVAY TOWNSHIP

Located In: Corner Code #

FILED

11/28/1995 09:37:05
REGISTER OF DEEDS
PAULA JOHNSON
INGHAM COUNTY, MI

- 1. Public Land Survey T 2N R 1W L-8
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims



Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. Cell (8, J) contains the number 2.

RONALD L. ENGER, in a field survey on OCTOBER 18, 19 95

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. ORIGINAL POST SET BY ANSON JACKSON, COUNTY SURVEYOR AND RECORDED IN VOLUME 1, PAGE 36 OF COUNTY SURVEY RECORDS IN JULY 1839 AND TWO BEARING TREES RECORDED: TAMRACK 8" S13E 16-1/2 LKS TAMRACK 14" N13-1/2E 25 LKS

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND 1/2" BAR IN OLD ANCHOR POST. EXCAVATED ALL AROUND ANCHOR POST AND FOUND ORDINARY STONES. PULLED IRON AND FOUND CAP #18998 LESTER ON BOTTOM. ACCEPTED ANCHOR POST AS CORNER AND STANDARD MARKER FOR PA 345 REMONUMENTATION IN INGHAM COUNTY IN ITS PLACE. SET 5' OF 1-1/2" PIPE 4' ABOVE GROUND NEXT TO IRON.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-8 T2N R1W
3/4" DIAMETER X 24" LONG SMOOTH STEEL BAR AND CAP IMPRINTED "PA 345 PS 28409" IN ANCHOR POST WITH 5' OF 1-1/2" GUARD POST
NAIL AND TAG #17640 (G. YOUNG) IN NORTH SIDE OF 10" SWAMP OAK, 79° NAZ., 27.75'
SET 20D GALVANIZED SPIKE AND TAG PS 28409 IN WEST SIDE OF 24" MAPLE, 171° NAZ., 59.55'
SET 20D GALVANIZED SPIKE AND TAG PS 28409 IN WEST SIDE OF 12" QUAD-TRUNK MAPLE, 4° NAZ., 63.45'
SET 20D GALVANIZED SPIKE AND TAG PS 28409 IN EAST SIDE OF 12" WHITE PINE, 301° NAZ., 74.60'

Signed by [Signature] Date NOVEMBER 1, 1995
Surveyor's Michigan License No. 28409

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

P.A. 345 INGHAM COUNTY
PEER APPROVED: 11/21/95 [Signature]

L-8 T2N R1W
PART A CONTINUED

2. R. STEADMAN, PS 11370 USED CORNER IN FEBRUARY 1972 IN A SURVEY RECORDED IN LIBER 1 OF SURVEYS, PAGE 222 WITH THE FOLLOWING WITNESSES:

WOOD ANCHOR POST

14" PINE, N86E, 6' (DEAD OCTOBER 1995)

6" POPLAR, N5W, 17' (DEAD OCTOBER 1995)

5" ELM, WEST, 33' (DEAD OCTOBER 1995)

3. R. LESTER, PS 18998 RECORDED CORNER IN MAY 1975 IN LIBER 3 OF CORNERS, PAGE 415 AND USED IN A SURVEY IN MAY 1975 IN LIBER 2 OF SURVEYS, PAGE 448 WITH THE FOLLOWING WITNESSES:

1/2" BAR AT BROKEN ANCHOR POST

NAIL AND TAG EAST SIDE OF 5" POPLAR, NORTH-NORTHEAST, 25.29' (DEAD OCTOBER 1995)

NAIL AND TAG EAST SIDE OF 10" POPLAR, NORTH-NORTHWEST, 16.84' (DEAD OCTOBER 1995)

NAIL AND TAG EAST SIDE OF 4" POPLAR, NORTHWEST, 18.72' (DEAD OCTOBER 1995)

4. M. MAHIEU, PS 28414 RECORDED CORNER IN LIBER 7, PAGE 207 AND USED IN AN ACT 132 SURVEY IN LIBER PAGE IN APRIL 1990 AS A FOUND 1/2" ROD AS RECORDED IN LIBER 3, PAGE 415 WITH THE FOLLOWING WITNESSES:

NAIL AND TAG WEST SIDE OF 12" OAK, N15°E, 25.29'

NAIL AND TAG NORTH SIDE OF 6" ELM, N75°W, 8.86'

NAIL AND TAG NORTH SIDE OF 6" ELM, S75°W, 7.07'

NAIL AND TAG NORTH SIDE OF 12" OAK, N80°E, 27.79'

RECORDED
LIBER 8
PAGE 548
1995