


LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in INGHAM VEVAY TOWNSHIP

Located In: Corner Code #

- 1. Public Land Survey T 2N R 1W L-9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims



FILED

11/28/1995 09:37:07
REGISTER OF DEEDS
PAULA JOHNSON
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

I, RONALD L. ENGER, in a field survey on OCTOBER 18, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. POST SET IN ORIGINAL GOVERNMENT SURVEY BY HERVEY PARKE, DEPUTY SURVEYOR IN FEBRUARY, 1826 AND TWO BEARING TREES RECORDED:
W. OAK 24" N59E 27 LKS
B. ASH 14" S67W 22-1/2 LKS

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND GOT MAGNETIC READING 3.2' SOUTH OF CENTERLINE OF ROLFE ROAD ON FENCE LINES NORTH AND SOUTH. EXCAVATED 1.5' X 1' HOLE AROUND READING AND FOUND WHAT WE INITIALLY THOUGHT WAS A BOAT SPIKE BUT TURNED OUT TO BE A 1/2" REBAR, 8" LONG. EXPANDED HOLE TO 3' X 3' X 4' DEEP. DID NOT GET THROUGH ROAD FILL AND FOUND NO OTHER EVIDENCE OF CORNER. ACCEPTED 1/2" BAR AS PERPETUATION OF CORNER AND SET STANDARD MARKER FOR PA 345 REMONUMENTATION IN INGHAM COUNTY IN ITS PLACE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-9 T2N R1W
3/4" SMOOTH STEEL BAR AND CAP IMPRINTED "PA 345 PS 28409" IN MONUMENT BOX 3' SOUTH OF CENTERLINE OF ROLFE ROAD.
SET 20D GALVANIZED SPIKE AND TAG PS 28409 IN WEST SIDE OF 15" OAK, 330° NAZ., 81.35'
SET 20D GALVANIZED SPIKE AND TAG PS 28409 IN WEST SIDE OF 22" OAK, 4° NAZ., 46.75'
NAIL AND TAG #21565 IN SOUTH SIDE OF 39" OAK, 68° NAZ., 72.78'
SET 20D GALVANIZED SPIKE AND TAG PS 28409 IN WEST SIDE OF 33" WILLOW, 176° NAZ., 37.45'
1/2" BAR AND CAP #3276, 4° NAZ., 33.00'
1/2" BAR AND CAP #21565, 184° NAZ., 33.00'

Signed by [Signature] Date NOVEMBER 1, 1995

Surveyor's Michigan License No. 28409

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 21, REVISED MAY 14, REVISED JAN.,

P.A. 345 INGHAM COUNTY
PEER APPROVED 11/21/95

Grid table with columns A-L and rows 2-13, containing numbers 6 through 36.

L-9 T2N R1W
PART A CONTINUED

2. ANSON JACKSON, COUNTY SURVEYOR, USED CORNER IN JULY 1839 RECORDED IN VOLUME 1, PAGE 36 WITH THE FOLLOWING WITNESSES:
BEECH 24" N59E 27 LKS
ASH 14" S67W 22-1/2 LKS
3. A. P. DRAKE, COUNTY SURVEYOR, USED CORNER IN DECEMBER 1882 RECORDED IN VOLUME 3, PAGE 191 AS A POST WITH THE FOLLOWING WITNESS:
W.O. 20" S1/4E 2 LKS.
4. THE PRIVATE RECORDS OF LAVERNE HENDRYX, NOW IN THE POSSESSION OF ACCOLADE SURVEYING, CALL FOR THE CORNER AS A #4 BAR IN AN UNRECORDED SURVEY DATED DEC. 6, 1975.
15" SWAMP OAK NNW 46.75'
28" SWAMP OAK ENE 73.35'
18" WILLOW SSE 37.6'
#4 IRON N. 33.0'
5. M. DYER, PS #21565 RECORDED CORNER IN JANUARY 1976 IN LIBER 3 OF CORNERS, PAGE 516, AS A FOUND 1/2" BOAT SPIKE 3.2' SOUTH OF CENTERLINE OF ROLFE ROAD ON FENCE LINE NORTH-SOUTH WITH THE FOLLOWING WITNESSES:
1/2" BAR AND CAP #3276 NORTH 33.00'
NAIL AND TAG EAST SIDE OF 15" OAK, NORTH 46.84'
NAIL AND TAG WEST SIDE OF 18" WILLOW, SOUTH 37.68'
NAIL AND TAG SOUTH SIDE OF 24" OAK, ENE 72.89'
6. M. DYER USED CORNER IN JANUARY 1976 IN A SURVEY RECORDED IN LIBER 2 OF SURVEYS, PAGE 604, WITH THE SAME MONUMENTS AND WITNESSES AS PART A-4.
7. G. YOUNG, PS #17640, USED CORNER IN MAY 1976 IN A SURVEY RECORDED IN LIBER 2 OF SURVEYS, PAGE 714, WITH THE FOLLOWING WITNESSES:
BOAT SPIKE
N & W IN 24" OAK, N45E, 72.87', (FOUND OCTOBER 1995)
N & W IN 15" OAK, NORTH 46.80', (FOUND OCTOBER 1995)
N & W IN 15" OAK (ACTUALLY A WILLOW), S05°E, 37.68', (FOUND OCTOBER 1995)
8. R. LESTER, PS 18998, USED CORNER IN NOVEMBER AND DECEMBER 1977 IN A SURVEY RECORDED IN LIBER 3 OF SURVEYS, PAGES 196 AND 284, WITH THE SAME MONUMENTS AND WITNESSES AS IN PART A-4.
9. A. WILLIAMS, PS 21275 USED CORNER IN JANUARY 1985 AND RECORDED IN LIBER 4 OF SURVEYS, PAGE 1010 WITH THE SAME MONUMENTS AND WITNESSES AS PART A-6.
10. G. YOUNG USED CORNER IN JULY 1989 AND RECORDED IN LIBER 5 OF SURVEYS, PAGE 1088 WITH THE SAME MONUMENTS AND WITNESSES AS PART A-6.
11. M. MAHIEU, PS #28414 USED CORNER IN NOVEMBER 1990 AND RECORDED IN LIBER 7 OF CORNERS, PAGE 203 WITH THE FOLLOWING WITNESSES:
1/4" BOAT SPIKE
NAIL AND TAG NORTH SIDE OF U.P., S80E, 136.92', FOUND OCTOBER 1995
NAIL AND TAG SOUTH SIDE OF 32" OAK, N60E, 72.74', FOUND OCTOBER 1995
NAIL AND TAG EAST SIDE OF 8" ELM N10E, 37.76'
NAIL AND TAG, NORTHEAST SIDE OF 6" B.E., N55W, 49.15'
12. M. MAHIEU USED CORNER IN AUGUST 1991 AND RECORDED IN LIBER 6 OF SURVEYS, PAGE 745 WITH THE SAME MONUMENT AND WITNESSES AS PART A-7.

SEARCHED
SERIALIZED
INDEXED
FILED
OCT 1995
FBI - MEMPHIS