

DEC 17 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 354

For corners in VEVAY TOWNSHIP

INGHAM COUNTY	Located In:	Corner Code #
1. Public Land Survey	T 2N R 1W	L-12
	T R	
	T R	
	T R	
2. Property Controlling In Section	S T R	
	S T R	
3. Miscellaneous Property In Sec.	S T R	
	S T R	

FILED

980049411
09/29/1998 10:51:52
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Maurice H. Mahieu, in a field survey on September 24, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. Corner not set in original GLO survey.
2. County Surveyor A. Jackson in collection of various surveys Vol. 1 P.24 notes W. Oak 34 S11E 11 1/2 Cherry 8 S 81 1/2 E 19, Sept. 6, 1845.
3. County Surveyor A. Jackson Vol. 1, P.93 notes W. Oak 34 S 11E 11 1/2 Cherry 8 S 81 1/2 E 19, Sept. 6, 1845.
4. County Surveyor A. Jackson L4A, P92 notes Cherry 8 S 81 1/2 E 19, Maple 12 N 84 1/2 E 21, Sept. 6, 1845.
5. County Surveyor A. Jackson in Folder Set #2 P.72B notes W. Oak 34 S 11E 11 1/2 links Cherry 8 S 81 1/2 E 19 links, November 7, 1856.
6. County Surveyor A. Jackson L3, P124 notes W. Oak 34 S 11E 11 1/2 Cherry 8 S 81 1/2 E 19, November 7, 1856.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35								
13													

(Continued On Back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron and cap #25832 0.5' West of North-South fence line and 0.5' North of East-West fence line. Found no witness tags. Accepted position of corner set by Surveyor Bryan as the perpetuated location set by previous County Surveyors. Pulled 1/2" iron rod and set 3/4" x 24" iron rod with aluminum P.A. 345 cap stamped "28414 - Ingham County". Measured 2644.81' to M-12; 2644.42' to L-11; 2648.73' to L-13; and 2648.32' to K-12.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1/2" iron rod with cap #25832, replaced with 3/4" x 24" iron rod and aluminum cap stamped #28414 Ingham County".

- Witnessed by:
- Set Nail and Tag #28414 North side 24" Oak, N 80° E, 7.99'
 - Set Nail and Tag #28414 South side Quadruple 10" Basswood, N 30° W, 21.02'
 - Set Nail and Tag #28414 West side 10" Hickory, South, 14.71'
 - Set Nail and Tag #28414 North side 12" Basswood, S 80° W 26.20'

Signed by Maurice H. Mahieu
Surveyor's Michigan License No. 28414

Date 9/22/98



P.A. 345 INGHAM COUNTY
PEER APPROVED 9/22/98 *mc*

A. (CONTINUED)

- 7. Notes from miscellaneous Ingham County Survey records Bk #15 P.118, Oak post set in ground witnessed by stump of Oak as recorded in the survey made by Jackson. Made new witnesses: B. Oak 12 N 47 1/2 E 49 1/2; DO 6 N 76 W 13; December 22, 1899.
- 8. County Surveyor E. A. Calkins in Folder Set #2 Page 72A notes 12 B. Oak, N 47 1/2 E 49 1/2 links; 6 B. Oak, N 76 W 13 links, December 22- 23, 1899.
- 9. County Surveyor E. A. Calkins in L1, Page 6 notes found oak post with stump of witness made by Jackson at proper distance from which post bears B. Oak 12, N 47 1/2° E, 49 1/2 lks DO 6, N 76° W, 13 lks, December 22-23, 1899.
- 10. LCRC recorded in Liber 6, Page 269 by Larry Bryan PS #25832 in March 29, 1985 "Set 1/2" bar at base of corner post, fence lines North, South & East, West corner called for in Folder 2, Page 72A of the Ingham County Remonumentation records." Witnesses: set Nail & Tag North side 20" Oak N 80° E 7.45'; Set Nail & Tag North side 8" Ash, West, 13.44'; Set Nail & Tag Southeast side 8" Hickory, S 50° W, 12.00'.

SURVEY & REMONUMENTATION

DEC 17 1998

SECTION

Rcpt No	97035
CMR	9.00
MSSR	2.00
Total	11.00