

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

INGHAM (County) Located In: Corner Code #
VEVAY TOWNSHIP
1. Public Land Survey T-2N R-1W M-8
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

FILED

11/28/1995 09:37:09
REGISTER OF DEEDS
PAULA JOHNSON
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 1-13. Contains numbers 1-36 in a grid pattern.

I, RONALD L. ENGER in a field survey on OCTOBER 11, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


A. Description of original monument and accessories and/or subsequent restoration:

1. POST SET IN ORIGINAL GOVERNMENT SURVEY BY JOSEPH WAMPLER, DEPUTY SURVEYOR ON FEBRUARY 7, 1824 AND TWO BEARING TREES RECORDED:
W. OAK, 21" N10 1/2W 111 LKS (73.3')
W. OAK, 20" S71W 153 LKS (101.0')

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND 1/2" PIPE AT EAST FACE TELEPHONE POLE FENCE POST. EXCAVATED ALL AROUND AND FOUND VAST AMOUNT OF TYPICAL RUN OF THE MILL FENCE POST STONES. ACCEPTED PIPE AS PERPETUATION OF CORNER AND CAPPED WITH PA 345 PS 28409 CAP.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-8 T2N R1W
1/2" PIPE WITH CAP IMPRINTED "PA 345 PS 28409" ON EAST SIDE OF NORTH-SOUTH-WEST FENCE CORNER.
NAIL AND TAG # 28409 IN EAST SIDE OF 30" WILD CHERRY, 0° NAZ., 21.00'
NAIL AND TAG # 11370 IN WEST SIDE OF 36" OAK, 178° NAZ., 31.95'
NAIL AND TAG # 11370 IN SOUTH SIDE WOOD FENCE POST, 270° NAZ., 12.19'
NAIL AND TAG # 18994 (RON HELSEL) IN NORTH SIDE OF 8" ASH, 98° NAZ., 53.89'

Signed by [Signature] Date OCTOBER 20, 1995
Surveyor's Michigan License No. 28409

