

DEC 1 2 1997

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Liber

9 Page 290

COMMISSION

For corners in  
VEVAY TOWNSHIP  
INGHAM COUNTY

Located In: Corner Code #

- 1. Public Land Survey      T 2N R 1W      M12  
                                   T    R  
                                   T    R  
                                   T    R
- 2. Property Controlling    S    T    R  
    in Section                S    T    R
- 3. Miscellaneous            S    T    R  
    Property in Sec.         S    T    R

**FILED**

970047153  
12/02/1997 13:38:30  
REGISTER OF DEEDS  
Paula Johnson  
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Maurice H. Mahieu, in a field survey on September 22, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1. ORIGINAL GLO CORNER WAS SET IN MAY/JUNE 1825 BY JOSEPH WAMPLER, D.S "40.00 Set 1/4 Sec. Post from which a W. Oak 14 N14W 11; Ash 13 S31W 27"

2. COUNTY SURVEYORS A. JACKSON IN 1845, A. JACKSON IN 1856, AND E. A. CALKINS IN 1899 ALL DID SURVEYS IN THE N.E. 1/4 OF SECTION 36 BUT NONE SHOWED ANY REFERENCE TO MONUMENTATION OR WITNESSES FOR THIS CORNER.

(See back for continuance)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND 1/2" IRON ROD IN CONCRETE MONUMENT IN THE CENTERLINE OF KELLY ROAD. KELLY ROAD HAS BEEN NEWLY WIDENED AND PAVED IN SEPTEMBER, 1997. ALL WITNESSES FROM A-3 WERE OBLITERATED AT TIME OF RECONSTRUCTION OF KELLY ROAD. 1/2" ROD AND MONUMENT ARE IN GOOD CONDITION. SET MONUMENT BOX OVER THE EXISTING IRON AND MONUMENT. LEFT IN PLACE AS THE MONUMENT IS THE CORRECT LOCATION FOR A LOST CORNER AS STATED IN LCRC LIBER 6, PAGE 69. Set cap #28414 on rod.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
1/2" IRON ROD IN CONCRETE MONUMENT WAS LEFT IN PLACE AND WITNESSES BY:  
NAIL & TAG #28414, WEST SIDE UTILITY POLE N9°E, 212.53 FEET  
NAIL & TAG #28414, EAST SIDE 12" HICKORY, N20°W, 74.33 FEET  
NAIL & TAG #28414, EAST SIDE 10" ELM, S52°W 33.17 FEET  
NAIL & TAG #28414, WEST SIDE UTILITY POLE, S19°E 74.75 FEET



Signed by Maurice H. Mahieu  
Surveyor's Michigan License No. 28414

Date 10-10-97

P.A. 345 INGHAM COUNTY  
PEER APPROVED 9/25/97

M12 VEVA  
PAGE 2

SECTION A - CONTINUED

3. LCRC RECORDED IN LIBER 6, PAGE 69 BY RONNIE M. LESTER / GARY D. LESTER, P.S. 18998/17624 ON AUG. 4, 1980. CORNER WAS RECORDED PART OF THE 1979/80 CETA INGHAM COUNTY REMONUMENTATION PROGRAM. \*EXCAVATED A HOLE 10'X10' TO AN AVERAGE DEPTH OF 3.0' ON THE CENTERLINE OF KELLY ROAD. FOUND BOARDS WITH NAILS AROUND NORTH AND SOUTH PERIMETER OF EXCAVATION SITE. APPEARS TO BE BROKEN FENCE LINE. FOUND PIECES OF FENCE ±2' BELOW ROAD SURFACE. NO OTHER EVIDENCE FOUND. CORNER CONSIDERED LOST. SET CORNER MIDWAY AND ON LINE BETWEEN M-13 AND M-11. MEASURED NORTH AND SOUTH 2648.75. MEASURED SOUTH TO A-13, 1358.97'; MEASURED NORTH TO A-12, 1262.59'. MONUMENT FALLS 10.2' WEST OF EAST EDGE OF KELLY ROAD. EXCAVATION CONDUCTED BY INGHAM COUNTY SURVEY AND REMONUMENTATION PROJECT CREW. SET 4"X36" CONCRETE MONUMENT WITH 1/2"X36" REBAR AND CAP #18998 IN LOCATION DESCRIBED ABOVE. WITNESSED BY:

NAIL & TAG #18998, NORTHEAST SIDE 8" BASSWOOD, ESE, 22.87'

NAIL & TAG #18998, WEST SIDE 24" BASSWOOD, SE, 35.82'

NAIL & TAG #18998, SOUTHWEST SIDE 24" OAK, SOUTH, 92.68'

NAIL & TAG #18998, EAST SIDE 8" HICKORY, NORTH 74.21'

4. AN ACT 132 SURVEY RECORDED IN LIBER 5, PAGE 47 BY GEORGE M. YOUNG, P.S. #17640 ON SEPT. 9, 1986 USED CORNER ON SURVEY. THE MONUMENTATION AND WITNESSES ARE THE SAME AS A-3

5. AN ACT 132 SURVEY RECORDED IN LIBER 5, PAGE 1238 AND RERECORDED IN LIBER 6, PAGE 669 ON DECEMBER 11, 1989 AND MARCH 8, 1991 BY THE SURVEYOR FOUND THE SAME MONUMENTATION AND WITNESSES AS A-3