

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 8 PAGE 209

FILED

For corners in

INGHAM
(County)

Located In: _____ Corner Code # _____

White Oak Township

1. Public Land Survey T 2N R 2E _____ A-5

T _____ R _____ _____

T _____ R _____ _____

T _____ R _____ _____

2. Property Controlling S _____ T _____ R _____ _____

in Section S _____ T _____ R _____ _____

3. Miscellaneous S _____ T _____ R _____ _____

Property in Sec. S _____ T _____ R _____ _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

SEP 14 8 43 AM '94

REGISTERED DEEDS
 State of Michigan
 TRENTHAM BUILDING, MICH.

Register of Deeds Stamp & File Number

I, R. W. Steadman, in a field survey on June 31, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: Wood post set by Joseph Wampler, U. S. Deputy Surveyor, 150 links north of M-5, T2N, R1E; bearing trees: 15" Ash S14-1/2°E 50 links and 5" Tamarack N86-3/4°E 40-1/2 links.
- 12-28-1839: Volume 1, Page 152, County Surveyor Anson Jackson used this corner, noting the original bearing trees for witnesses, but does not describe the monument.

(Continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron pipe and cap 11370 in good condition in monument box in center of Meech Road and about 5 feet North of center of Iosco Road. 1976 witnesses gone, except for M-5, T2N, R1E.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Left 1/2" iron pipe and cap 11370 in place as found in monument box to mark t corner, and took the following witnesses (bearings are magnetic):

- Set nail and tag 11370 in W. side 20" Walnut S33°W 141.39 feet
- Set nail and tag 11370 in SW side 12" Elm S16°E 131.82 feet
- Set nail and tag 11370 in SW side 20" Walnut S61°E 149.74 feet

(Continued on back)

Signed by Richard W. Steadman Date July 12, 1994

Surveyor's Michigan License No. 11370

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 11
 REVISED MAY 14, 11
 REVISED JAN., 11

P. A. 345 INGHAM COUNTY

PEER APPROVED 7/13/94 RL

A-5, T2N, R2E

Part A - Continued

- 3). 4-26-1976: Land Corner Recordation Certificate (Rec. 1-16-79, L5-P143), R. W. Steadman L.P.S. 11370 "dug hole in the intersection of Meech and Iosco Roads, but found nothing. Re-established the corner on the township line as defined by the quarter corner next north for T2N, R1E and the corresponding section corner for T2N, R1E (see Items 4). and 5). below), and at the USPLS recorded jog distance south of it. Set 1/2" iron pipe and monument box to mark the corner. Witnesses: telephone pole S20°E 80.71 ft., wood anchor post S64°E 87.64 ft., 20" Maple N71°E 76.17 ft. Corner for T2N, R1E (set 3/4" iron pipe and monument box - 1973) South 99 ft." Note: A-5 is North of M-5, not South of it.
- 4). 6-22-1973: Land Corner Recordation Certificate for M-4, T2N, R1E (Rec. 1-16-79, L5-P147), R. W. Steadman "dug hole in Meech Road opposite fence West, and about 2 ft. below the surface, found a long pointed stone with a hub cap alongside, and broken crockery and small stones around. Raised location of stone to surface with 3/4" iron pipe and set monument box. Witnesses: 24" Maple WNW 23.08 ft., 22" Maple SSE 131.51 ft., wood culvert post NNE 83.03 ft."
- 5). 6-25-1973: Land Corner Recordation Certificate for M-5, T2N, R1E (Rec. 1-16-79, L5-P146), R. W. Steadman "dug hole in the intersection of Meech and Iosco Roads but found nothing. Re-established corner by proportional measurements from possession evidence North, South, and West. Set 3/4" iron pipe in monument box to mark the corner. Witnesses: 30" Maple NNW 66.94 ft., 14" Walnut SSW 74.63 ft., Telephone pole SW 59.72 ft., Telephone pole NE 39.15 ft."

Part C - Continued

Set nail and tag 11370 in S. side 12" Elm N72°E 70.80 feet
 Set nail and tag 11370 in S. side 15" Elm N68°W 66.66 feet
 Found 1/2" iron rod and cap marked "Ingham Temp. Pt." S07°E 3.94 feet
 Found 1/2" iron pipe and cap 11370 in monument box (corner for T2N, R1E)
 S04°W 99.00 feet