

SURVEY &  
 REMONUMENTATION  
 APR 10 1995  
 COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

Oct 3 1 15 PM '94

For corners in  
INGHAM  
(County)

Located In: Corner Code =#

White Oak Township

1. Public Land Survey	T <u>2N</u>	R <u>2E</u>	<u>A-8</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

REGISTER OF DEEDS  
*Frank J. Anson*  
 INGHAM COUNTY, MICH.

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, R. W. Steadman, in a field survey on July 19, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1-12-1855: Volume 2, Page 242, County Surveyor Anson Jackson appears to have established this closing quarter corner, stating "no bearings", and giving no monument description. Establishment of closing quarter corners was not included in the procedure for the United States Survey of the Public Lands. I find no other reference to this corner in available records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found no monumentation at corner location. Set standard Ingham County Remonumentation 3/4" iron rod and cap on township line between standard corners M-7 (1/2" iron rod rec. in L2-P405) and M-8 (pointed stone rec. in L4-P75) for T2N, R1E, and on line with old fence running East.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" smooth iron rod and cap stamped "P. A. 345, PS 11370" and took the following witnesses (bearings are magnetic):

- Set nail and tag 11370 in N. side 5" Ash N74°E 5.92 feet
- Set nail and tag 11370 in SW side 8" quad. Hickory S56°E 10.61 feet
- Set nail and tag 11370 in E. side Anchor Post S21°W 20.31 feet
- Set nail and tag 11370 in S. side Fence Post N70°W 155.45 feet
- Found pointed stone (M-8, T2N, R1E) S03°W 18.58 feet

Signed by Richard W. Steadman Date September 9, 1994

Surveyor's Michigan License No. 11370

P.A. 345 INGHAM COUNTY  
 PEER APPROVED 9/14/94