

OCT 3 1 17 PM '94
REGISTER OF DEEDS
Richard W. Steadman
INGHAM COUNTY, MICH.

SURVEY & REMONUMENTATION
APR 10 1995
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in INGHAM (County)
White Oak Township

Located in: _____ Corner Code # C-5

1. Public Land Survey	T <u>2</u> N	R <u>2</u> E	_____
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

R. W. Steadman, in a field survey on June 14, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: Wood post set by Joseph Wampler, U. S. Deputy Surveyor; bearing trees: 14" Sugar S19°W 18 links and 3" Ironwood N55°E 12 links.
- I find no further mention of this corner in available records until the Land Corner Recordation Certificate listed in 3). below.

(Continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found concrete monument with cap 18998 in good condition in monument box in center of Iosco Road.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Left concrete monument with cap 18998 in monument box as found to mark the corner and took the following witnesses (bearings are magnetic):

- Found nail and tag 18998 in W. side Power Pole N10°E 25.42 feet
- Found nail and tag 18998 in E. side 15" Hickory S16°W 87.33 feet
- NW corner foundation House #3010 S19°E 189.71 feet
- Set nail and tag 11370 in SW side 22" Chinese Elm S33°E 41.15 feet
- Set nail and tag 11370 in S. side 28" Elm N76°E 83.54 feet

Signed by Richard W. Steadman Date September 9, 1994

Surveyor's Michigan License No. 11370
P.A. 345 INGHAM COUNTY
PEER APPROVED 9/14/94 M

C-5, T2N, R2E

Part A - Continued

- 3). 4-03-81: Land Corner Recordation Certificate (Rec. 6-04-81, L6-P193), R. M. Lester L.P.S 18998 indicates excavation was made but nothing found. Corner was re-established on road centerline opposite fence North. "Measured South 2687.66 feet, North 2643.24 feet, West 2668.97 feet, and East 2625.19 feet. Excavation by Ingham County Survey and Remonumentatio Project Crew". A 4" by 36" concrete monument with collar and cap 18998 was set and witnessed by: nail and tag 18998 in W. side Power Pole N10°E 25.44 feet, nail and tag 18998 in S. side 10" Hawthorne N70°E 83.65 feet, nail and tag 18998 in SW side 12" Cottonwood S70°E 41.47 feet, nail and tag in E. side 12" Hickory S10°W 87.38 feet.
- 4). 10-18-94: Private records of D. L. Clifford L.P.S. 25837 surveying for the subsequently cancelled Supercollider Project - surveyed Section 18, T2N, R2E, and established coordinates for the corners. Computation of distances from his coordinates indicates that it is 2687.52 feet South and 2668.61 feet West to the adjacent corners.