

FILED

NOV 1 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Oct 16 8 59 AM '95

REGISTER OF DEEDS  
*Frank Johnson*  
INGHAM COUNTY, MICH.

For corners in  
INGHAM  
(County)

Located In:

Corner Code #

White Oak Township

- 1. Public Land Survey      T 2N R 2E      C-8  
                                   T     R  
                                   T     R  
                                   T     R
- 2. Property Controlling    S     T     R  
    in Section               S     T     R
- 3. Miscellaneous           S     T     R  
    Property in Section    S     T     R

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, R. W. Steadman, in a field survey on August 22, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

- 1). 1825: Wood post set by Joseph Wampler, U. S. Deputy Surveyor; bearing trees: 12" Ash S72-1/2°W 9 links and 8" Ash N53-1/2°W 14 links.
- 2). 1-12-1855: Vol. 2, Page 242, County Surveyor Anson Jackson must have used this corner to set the section center, but he does not so state or indicate.

(Continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Ran traverse and computed position of corner from Clifford's coordinates, but was unable to recover his spike and tag. About 2 feet north found east-west fence (down), and about 1.5 feet east found remnants of fence wire running north. Elected to re-establish the corner at the intersection of the fences. From this corner location north to C-7 measures 2655.55 feet and south to C-9 measures 2650.36 feet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Ingham County Remonumentation 3/4" smooth iron rod and cap stamped "P. A. 345, PS 11370" and took the following witnesses (bearings are magnetic):

- C/L Ditch East 154 feet M/L
- C/L Ditch South 26 feet M/L
- Apex of large stone N61°E 4.89 feet

(Continued on back)



Signed by Richard W. Steadman

Date September 23, 1995

Surveyor's Michigan License No. 11370

C-8, T2N, R2E

Part A - Continued

10-18-1988: Private records of D. L. Clifford L.P.S. 25837, surveying for the subsequently cancelled Supercollider Project; surveyed north and east lines of this section, and in regard to this corner notes "Spike and tag at apparent 1/4 Corner".

Part C: - Continued

Set nail and tag 11370 in S. side 15" Maple East 21.55 feet  
Set nail and tag 11370 in E. side 15" Wild Cherry N50°W 43.09 feet  
Set nail and tag 11370 in S. side 40" Maple West 32.16 feet

2798