

DEC 1 8 06 AM '94

SURVEY & MONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

REGISTER OF DEEDS
Dana Johnson
INGHAM COUNTY, MICH.

For corners in
INGHAM COUNTY
(County)

Located In: Corner Code #

WHITE OAK TOWNSHIP
1. Public Land Survey T 2N R 2E C-13
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, David L. Clifford a field survey on April 23, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original Post set by J. Wampler D.S. in Aug. 1824
W.O. 20 N51E 6 (4.0')
Maple 9 N58E 98 1/2 (65.0')
- Corner Used by W.A. Rowe Co. Surveyor in Oct. 1895 recorded in Field book 15 page 26 in which he stated that he found the original post and witnesses in good condition and he found the original post at the N.W. Corner of Sec. 5 Stockbridge in good condition and in the proper relationship to the S.W. Cor. of Sec. 32 White Oak Township. OVER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Searched at aparent location of corner and found Anchor Post hole 213.2 feet East of C1 Stockbridge Township This being the exact GLO falling I accepted Post Hole as location of corner and set Standard Bar & PA 345 Cap in Center of large mound of stone after excavating around post hole and finding a fantastic amount of run of the mill fence post stones. Measured East 2631.43' to D13 White Oak Township.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Standard 3/4" Steel Bar and PA 345 Cap PS #25837 in Anchor Post Hole At East-West-North Fence Corner

Set Nail & Tag#25837 in S. Side 12" Hick. Naz 98° 40.42'
Set Nail & Tag#25837 in W. Side 36" Map. Naz 190° 39.91'
Set Nail & Tag#25837 in W. Side 14" Hick. Naz 217° 49.93'
Set Nail & Tag#25837 in SE Side 22" Swamp Oak Naz 238° 25.74'
3/4" Pipe (C-1, T1N, R2E) Naz 272° 213.20'

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2			
3												
4	7		8		9		10		11			
5												
6	18		17		16		15		14			
7												
8	19		20		21		22		23			
9												
10	30		29		28		27		26			
11												
12	31		32		33		34		35			
13												



Signed by Dave Clifford
Surveyor's Michigan License No. 25837

Date Oct. 11 1994

2749

P.A. 345 INGHAM COUNTY
PEER APPROVED 10/12/94

3. George Young L.S. #17640 recorded corner in Liber 3 of
corners page 325 in Jan. 1975 as an anchor post.

LIBER

8 PAGE 392

Nail in 24" Maple South 39.95'

Nail in 12" Hick. S40°W 49.57'

Nail in 18" Oak S50°W 25.76'

4. George Young used corner in surveys recorded in liber 2
of surveys page 263 in Jan. 1975 and liber 2 page 327
in April 1975 with the same mon. & witnesses as in item
3.

2749

8 301