

SURVEY & MONUMENTATION COMMISSION
APR 10 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 1 8 05 AM '94

For corners in
INGHAM
 (County)

Located In: Corner Code #

WHITE OAK TOWNSHIP
 1. Public Land Survey T 2N R 2E D-13
 T R
 T R
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

REGISTER OF DEEDS
 INGHAM COUNTY, MICH.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

I, Dave Clifford, in a field survey on September 3, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1. Original Post set by J. Wampler D.S. in Aug. 1824
 B.O. 12 N61W 66(43.56')
 W.O. 9 N26E 110 (72.6')
 2. Corner used by A. Jackson Co. Surv. in June 1854 recorded in Vol 2 Page 206 with same mon. & Wit. as in item 1.
 3. Corner Used by W.A. Rowe Co. Surveyor in Oct. 1895 recorded in Field book 15 page 26 in which he stated that he set a gas pipe for post based on proration of A. Jacksons survey. W.O. 30" N31 3/4°W 321 1(211.86')
 W.O. 24" S88 3/4°E 453 1/2 1(299.31')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Searched at apparent location of corner and found Anchor Post hole 195.36 feet East of D1 Stockbridge Township. Measured N32°W 211.9' to remains of W.A. Rowe's Oak witness (now badly deteriorated oak stump). Accepted post hole as corner because of agreement of both distances with Rowe's distances of 1895. Drove standard bar in post hole & capped with PA 345 cap.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set Standard 3/4" Steel Bar and PA 345 Cap PS #25837 in Anchor Post Hole At West-North Fence Corner

Set Nail & Tag#25837 in E. Side 10" Apple Naz 32° 14.31'
 Set Nail & Tag#25837 in W. Side 6" Mult. Cherry Naz 340° 28.57'
 Centerline 6" Steel Fence post (Guy post) Naz 270° 8.63
 3/4" Bar & PA 345 Cap PS 25837(D-1, T1N,R2E) Naz 270° 195.36'

Signed by Dave Clifford Date November 8, 1994

Surveyor's Michigan License No. 25837

2743

P.A. 345 INGHAM COUNTY
 PEER APPROVED 10/12/94