

**SURVEY &
REMONUMENTATION**

DEC 09 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

INGHAM COUNTY
(County)

Located In:

Corner Code #

WHITE OAK TOWNSHIP
1. Public Land Survey

T 2N R 2E

K-10

Paula Johnson
INGHAM COUNTY
REGISTER OF DEEDS
ENGER SURVEYING & ENGINEERING

L-9 P-550

RECORDED
CRNR 9.00

1999-060040



1999-060040

Page: 1 of 1
11/30/1999 09:48A

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, DAVID L. CLIFFORD, in a field survey on AUG. 26, 1999 Do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1. POST SET IN ORIGINAL GOVERNMENT SURVEY BY J. WAMPLER, D.S., IN NOV. 1825; WHITE OAK 20, N88½E 12 LKS; WHITE OAK 20, N5½E 48 LKS.

2. T.J. BROWN COUNTY SURVEYOR CALLS FOR CORNER IN A SURVEY RECORDED IN VOLUME 2 PAGE 330 IN MARCH 1858 IN THE INGHAM COUNTY SURVEYOR RECORDS WHICH HAS NO MENTION OF MONUMENTATION: WHITE OAK 20", N88½E 12 LKS; WHITE OAK 20", N5½E 48 LKS.

3. RONNIE M. LESTER RLS #18998 RECORDED CORNER IN LIBER 6 PAGE 160 IN MARCH 1981 AS FOUND 1/2" BAR IN MIDDLE OF MANY STONES AND SET 4" X 36" CONCRETE MONUMENT WITH 1/2" X 38" REBAR AND CAP RLS #18998 IN PLACE OF 1/2" BAR: NAIL AND TAG #18998 SOUTHEAST SIDE 6" MAPLE, NORTH 3.73'; NAIL AND TAG #18998 EAST SIDE 8" MAPLE, NORTH 22.30'; NAIL AND TAG #18998 SOUTHEAST SIDE LIGHT POLE, NE 81.47'; NAIL AND TAG #18998 WEST SIDE 20" MAPLE, SSE 41.75'.

4. GEORGE M. YOUNG R.L.S. #17640 USED CORNER IN ACT 132 SURVEY RECORDED IN LIBER 4 PAGE 550 OF SURVEYS IN JULY 1982: NAIL AND TAG #18998 SOUTHEAST SIDE 6" MAPLE, NORTH 3.73'; NAIL AND TAG #18998 EAST SIDE 8" MAPLE, NORTH 22.30'; NAIL AND TAG #18998 SOUTHEAST SIDE LIGHT POLE, NE 81.47'; NAIL AND TAG #18998 WEST SIDE 20" MAPLE, SSE 41.75'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND CONCRETE MONUMENT AND CAP #18998 IN OLD ANCHOR POST HOLE SURROUNDED BY STONES. CORNER MATCHED 3 LESTER WITNESSES. ACCEPTED CONCRETE MONUMENT AS CORNER AND CAPPED WITH STANDARD CAP. MEASURED 2663.82' NORTH TO K-9 AND 2656.54' SOUTH TO K-11.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10 T2N-R2E
4" CONCRETE MONUMENT WITH 1/2" BAR AND 2¼" ALUMINUM CAP STAMPED PA 345 25837 INGHAM COUNTY
SET NAIL AND TAG #28409 (RON ENGER) EAST SIDE 19" MAPLE, S52°W 22.30'
SET NAIL AND TAG #28409 EAST SIDE 19" MAPLE, S32°W 25.52'
FOUND NAIL AND TAG #18998 EAST SIDE LIGHT POLE, N32°E 81.42'
SET NAIL AND TAG #28409 WEST SIDE 23" MAPLE, NORTH 3.90'



Signed by David Clifford
Surveyor's Michigan License No. 25837

Date SEPTEMBER 09, 1999

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983
REVISED OCT., 1996

P.A. 345 INGHAM COUNTY
PEER APPROVED: 10/29/99 M