

SURVEY & REMONUMENTATION

DEC 09 1999

Paula Johnson  
INGHAM COUNTY  
REGISTER OF DEEDS RECORDED  
ENGER SURVEYING & ENGINEERING CRNR 9.00

L-9 P-498

1999-050560

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>INGHAM COUNTY</u> (County)	Located In:	Corner Code #
<u>WHITE OAK TOWNSHIP</u>	<u>T 2N R 2E</u>	<u>L-2</u>
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____



1999-050560  
Page: 1 of 1  
10/08/1999 02:29P

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, DAVID L. CLIFFORD, in a field survey on APRIL 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3													
4	7		8		9		10		11				
5													
6	10		17		16		15		14				
7													
8	19		20		21		22		23				
9													
10	30		29		28		27		26				
11													
12	31		32		33		34		35				
13													

A. Description of original monument and accessories and/or subsequent restoration:  
1. CORNER NOT SET IN ORIGINAL GOVERNMENT SURVEY.

2. A. JACKSON, COUNTY SURVEYOR, SET CORNER IN A SURVEY RECORDED IN VOLUME 1 PAGE 150 IN NOVEMBER 1838 WITH NO MENTION OF MONUMENT OR WITNESSES. HE STATES "IN MARSH"

3. GARY BOSS, RLS, 17022, RECORDED CORNER IN LIBER 5 PAGE 1 IN OCTOBER 1978 AND USED IT IN AN ACT 132 SURVEY RECORDED IN LIBER 3 PAGE 222 IN OCTOBER 1978 AS A 1/2" IRON SET AT FENCE INTERSECTION NORTH AND WEST: NAIL N/S 6" ELM, WEST, 33.18'; NAIL W/S TREE CLUMP, N30°W, 32.58'; NAIL NORTH SIDE TREE CLUMP, S80°W, 29.78.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND 1/2" BAR & CAP #17022 AT NORTH-WEST FENCE CORNER. IRON IS IN FAIR PROPORTION TO JACKSONS 1838 SURVEY (AS GOOD AS CAN BE EXPECTED LOOKING AT THE TERRAIN HE HAD TO CHAIN THROUGH). IRON IS 9' NORTH AND 13' EAST OF THE INTERSECTION OF 1/4 LINES. ACCEPTED 1/2" BAR & CAP AS PERPETUATION OF CORNER AND REPLACED IT WITH STANDARD BAR & CAP. MEASURED WEST 2639.05' TO K-2. MEASURED NORTH 3414.69' TO L-1. MEASURED EAST 2666.12' TO M-2. MEASURED SOUTH 2619.21' TO L-3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-2 T2N, R2E

3/4" X 24" BAR WITH 2 1/2" ALUMINUM CAP IMPRINTED PA 345 INGHAM COUNTY 25837 AT NORTH-WEST FENCE CORNER  
NAIL & TAG 25837 IN WEST SIDE 6" BOX ELDER, S10°W, 49.85'  
NAIL & TAG 25837 IN SOUTH SIDE 12" BOX ELDER, N77°W, 33.00'  
NAIL & TAG 25837 IN NORTH SIDE 10" COTTONWOOD, S85°E, 149.40'  
NAIL & TAG 28409 (RON ENGER) IN WEST SIDE 23" WILLOW, N07°W, 91.04'



Signed by David Clifford  
Surveyor's Michigan License No. 25837

Date SEPTEMBER 03, 1999

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971  
REVISED MAY 14, 1976  
REVISED JAN, 1983  
REVISED OCT, 1986

P.A. 345 INGHAM COUNTY  
PEER APPROVED 9/21/99 RL