

DEC 17 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 423

SECTION
For corners in

<u>INGHAM COUNTY</u>	Located In:	Corner Code #
(County)		
WHITE OAK TOWNSHIP		
1. Public Land Survey	T <u>2N</u> R <u>2E</u>	<u>L-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED

980060999
12/01/1998 09:36:13
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DAVID L. CLIFFORD, in a field survey on SEPTEMBER 24, 19 98
Do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- JOSEPH WAMPLER D.S. SET POST IN ORIGINAL GOVERNMENT SURVEY IN NOVEMBER 1825 B.O. 5" N39°E 45 LKS; B.O. 7" S82°E 65 LKS;
- T.J. BROWN, DEPUTY COUNTY SURVEYOR, USED CORNER IN SURVEYS RECORDED IN VOLUME 2 PAGE 329 & 330 IN JAN. & MARCH 1858 WITH SAME MONUMENT AND 1ST WITNESS OF GLO;
- GEORGE YOUNG RLS # 17640 RECORDED CORNER IN LIBER 4 OF CORNERS PAGE 97 IN JUNE 1977 AND USED IT IN SURVEYS RECORDED IN LIBER 3 OF SURVEYS PAGE 28 IN JUNE 1977 AS A SET 1/2" BAR & CAP IN OLD ANCHOR POST HOLE FOUND AFTER 10' DIAMETER EXCAVATION; #16 NAIL & CAP IN 36" OAK, N05°W, 14.57'; #16 NAIL & CAP IN 24" OAK, S30°W, 49.60'; #16 NAIL & CAP IN TWIN 12" OAK, S89°W, 49.11';
- MAURICE MAHIEU RLS #28414 USED CORNER IN A SURVEY RECORDED IN LIBER 5 OF SURVEYS PAGE 1231 IN NOVEMBER 1989 AS A FOUND 1/2" IRON ROD; 15" ASH N75°E 106.42'; 6" ELM S45°W 18.92'; 36" OAK S50°E 142.28' (THESE WITNESSES ARE GEORGE YOUNG'S WITNESSES TO K-11)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND A 1/2" REBAR & CAP IN OLD ANCHOR POST HOLE 3' WEST OF NEWER FENCE TO NORTH. THE EAST WEST POSITION OF THIS IRON COMPARES FAIRLY WELL WITH BROWNS SURVEY OF 1858 BUT IS ON THE NORTH FENCE LINE OF ABANDONED GILLIAM ROAD. EXCAVATED 15' DIAMETER HOLE IN CENTERLINE OF OLD ROAD BED 25' SOUTH OF FOUND IRON. FOUND NO FURTHER EVIDENCE OF CORNER. CONSIDERED CORNER OBLITERATED AND SET STANDARD MONUMENT ON SECTION LINE OPPOSITE ANCIENT FENCE TO NORTH 22.02' SOUTH OF IRON RECORDED AS K-11. MEASURED WEST 2656.55' TO K-11. MEASURED EAST 2648.83 TO M-11.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-11 T2N-R2E
- 3/4" BAR X 24" SMOOTH STEEL BAR & 2 1/2" ALUMINUM CAP STAMPED PA 345 LS 25837 INGHAM COUNTY
- SET NAIL & TAG #25837, EAST SIDE 40" OAK, N05°W, 35.50'
- SET NAIL & TAG #25837, WEST SIDE 10" ELM, N38°E, 6.95'
- SET NAIL & TAG #25837, NW SIDE 15" DOUBLE OAK, S57°W, 33.90'
- SET NAIL & TAG #25837, NORTH SIDE 20" DOUBLE OAK, S85°W, 84.40'
- SET NAIL & TAG #25837, NORTH SIDE 14" OAK, N79°W, 44.70'
- 1/2" BAR & CAP (IRON RECORDED AS K-11), N3°E, 22.02'

Signed by David Clifford
Surveyor's Michigan License No. 25837

Date OCTOBER 20, 1998



P.A. 345 INGHAM COUNTY
PEER APPROVED: 11/4/98 MC