

**SURVEY & REMONUMENTATION**

DEC 09 1999

Paula Johnson  
INGHAM COUNTY  
REGISTER OF DEEDS RECORDED  
ENGINEER SURVEYING & ENGINEERING CRNR 9.00

**L-9 P-502**

1999-050564

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

INGHAM COUNTY Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)  
WHITE OAK TOWNSHIP  
1. Public Land Survey T 2N R 2E M-3  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section T \_\_\_\_\_ R \_\_\_\_\_  
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_



1999-050564  
Page: 1 of 1  
10/08/1999 02:29P

Register of Deeds Stamp & File Number

I, DAVID L. CLIFFORD, in a field survey on MAY 27, 1999. Do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1. POST SET IN ORIGINAL GOVERNMENT SURVEY BY J. WAMPLER, D.S., IN DEC. 1824; CHERRY 9, N21 1/2 W, 25 1/2 LKS; W.O. 11, N85 W, 30 1/2 LKS.

2. A. JACKSON, COUNTY SURVEYOR, USED CORNER IN A SURVEY RECORDED IN VOLUME 1 PAGE 149, IN NOV. 1838 IN THE INGHAM COUNTY SURVEYOR RECORDS WITH THE SAME WITNESSES AS GLO.

3. TJ BROWN, COUNTY SURVEYOR USED CORNER IN A SURVEY RECORDED IN VOLUME 2 PAGE 367 IN JAN. 1860 IN THE INGHAM COUNTY SURVEYOR RECORDS WITH NO MENTION OF MONUMENT AND THE GLO W.O. WITNESS.

4. RONNIE M. LESTER RLS 18998 RECORDED CORNER IN LIBER 5 PAGE 235 IN APRIL 1979 DURING THE INGHAM COUNTY REMONUMENTATION PROGRAM OF THE LATE 1970'S. HE REPORTED A 9' X 5' EXCAVATION 3' DEEP AT THE INTERSECTION OF COLUMBIA AND KANE ROADS, 96' FEET NORTH OF 3/4" BAR FOUND AT THE LOCATION OF A-3, T2N, R3E. EXCAVATION REVEALED A 1/2" BAR ON THE CENTERLINE OF COLUMBIA ROAD AND 1.5' EAST OF CENTERLINE OF KANE ROAD. THE EXCAVATION ALSO REVEALED A 9" X 6" X 3" POINTED ROCK ON CENTERLINE COLUMBIA AND 1.5' WEST OF CENTERLINE KANE. AFTER MEASUREMENTS WERE MADE TO L-3 AND K-3 THE STONE WAS EXCEPTED AS CORNER AND REPLACED WITH CONC. MONUMENT AND CAP: NAIL & TAG, # 18998, SW SIDE 40" MAPLE, SE, 30.10'; NAIL & TAG, # 18998, SW SIDE 12" HICK., SW, 43.48'; NAIL & TAG, # 18998, SOUTH SIDE 18" OAK, ENE, 26.37'; NAIL & TAG, # 18998, SOUTH SIDE 12" WALNUT, WSW, 73.21'; 3/4" IRON IN CENTER OF KANE ROAD AND ON FENCE LINE TO EAST, SOUTH, 96.24'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND 4" CONC. MONUMENT WITH ILLEGIBLE CAP 1' WEST OF CENTERLINE KANE ROAD ON CENTERLINE COLUMBIA ROAD TO WEST AGREEING WITH R. LESTER WITNESSES. ACCEPTED MONUMENT AS PERPETUATION OF CORNER AND CAPPED IT WITH STANDARD ALUMINUM CAP. MEASURED NORTH 2637.90' TO M-2. MEASURED WEST 2672.39' TO L-3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


M-3 T2N-R2E  
4" CONC. MONUMENT WITH 1/2" BAR AND 2 1/4" ALUMINUM CAP STAMPED PA 345 25837 INGHAM COUNTY

SET NAIL & TAG 25837, SOUTH SIDE 23" OAK, N83°E, 26.49'  
FOUND NAIL & TAG 18998, SW SIDE 40" MAPLE, S49°E, 30.04'  
FOUND NAIL & TAG 18998, SE SIDE 18" HICKORY, S37°W, 43.50'  
SET NAIL & TAG 25837, NORTH SIDE 23" WALNUT, S83°W, 73.10'  
SET NAIL & TAG 25837, SOUTH SIDE 46" OAK, N68°W, 107.52'  
3/4" BAR (A-3, T2N, R3E) SOUTH, 96.25'

Signed by David Clifford

Date JULY 07, 1999

Surveyor's Michigan License No. 25837



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1976  
REVISED JAN. 1983  
REVISED OCT. 1996

P.A. 345 INGHAM COUNTY  
PEER APPROVED 8/17/99 AC