

Part A Continued

5. An Act 132 survey in Liber 1, Pages 271-272 recorded by Ronnie Lester PS A#18998 on June 1, 1972 calls for a 1/2" bar witnessed by:
Nail and Tag East side 24" Maple, NNW 236.75'
South corner of stone well, NE 121.00'
6. An Act 132 survey in Liber 1, Page 766 recorded by Richard Steadman PS #11370 on June 5, 1973 calls for a 1/2" bar witnessed by:
Nail and Tag in 24" Maple, NNW 236.75'
South corner of stone wall, NE 121.00'
7. LCRC recorded in Liber 2, Page 629 by Richard Steadman PS #11370 on January 18, 1974 calls for Set 3/4" iron pipe and cap witnessed by:
Nail and Tag in Telephone Pole, NNE 91.25'
Nail and Tag in Telephone Pole, ESE 63.73'
Narrative of LCRC states excavation was performed but no definite monumentation was found. Corner was set from R. J. Robb of 1910.
8. LCRC recorded in Liber 3, Page 231 by Ronnie Lester PS #18998 and Richard Steadman PS #11370 on September 20, 1974 agree to the monument filed in Liber 1, Page 539 to represent the corner. Witnessed by:
South Corner of Stone Well, NNE 121.00'
Nail and Tag in South side of Power Pole, NW 94.69'
Nail and Tag in West side of Power Pole, SSE 86.84'

Narrative of LCRC states "The following are pertinent: (1) The original monument and accessories are non-existent, and the monument of recorded restoration could not be found; (2) The record evidence is insufficient to show conclusively that either monument occupies the position of the original; (3) Modern surveys have been made using the monument recorded in Liber 1, Page 539, but none using the one recorded in Liber 3, Page 231.

In view of the above and in the interest of establishing a uniform and consistent system of surveys, the undersigned Land Surveyors have agreed to use the monument filed in Liber 1, Page 539 to represent the corner".
9. An Act 132 survey in Liber 4, Pages 751-752 recorded by Peter Beaver PS #25838 on September 15, 1983 calls for a 1/2" iron pipe and cap witnessed by:
South Corner of Stone Well, NNE 121.00'
Nail and Tag in South side of Power Pole, NW 94.69'
Nail and Tag in West side of Power Pole, SSE 86.84'
10. An Act 132 survey in Liber 5, Pages 22-23 recorded by Kay Don Fluke PS #18988 on August 14, 1986 calls for a 1/2" bar recorded in Liber 1, Page 539 (Act 74).
11. An Act 132 survey in Liber 6, Pages 275-276 recorded by David Lohr PS #30090 on July 31, 1990 calls for a 1/2" iron pipe and cap witnessed by:
Southwest Corner, found NNE 121.00'
Nail and Tag South side Power Pole, NW 94.69'
Nail and Tag West side Power Pole, SSE 86.84'
Nail and Tag Utility Pole, N15E 84.20'
SE Cor. Sec. 13, T2N, R3W No. 82.40'

TOWN OF COVINGTON
 CLERK OF COURTS
 REGISTER OF DEEDS
 MASSACHUSETTS
 2000-2003
 RECORDED
FILED

FILED

2000

30