

REMONUMENTATION

DEC 12 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 292

For corners in AURELIUS TOWNSHIP

INGHAM COUNTY	Located In:	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>2W</u>	<u>A-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____	_____
	S _____ T _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____	_____
	S _____ T _____	_____

FILED

970047754
12/02/1997 13:38:32
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Maurice H. Mahieu, in a field survey on September 26, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- This corner was not set in the original GLO survey.
- County Surveyor A. Jackson on February 10, 1852 used corner. No corner material recorded; witnessed by: Maple 24 S 69 1/2 E 40 1/2 lks; B Ash 24 N44E 80 1/2. Record in Book 1, Page 271.
- County Surveyor A. Jackson on December 21, 1854 used corner. No corner material noted, same witness as A-2. Recorded in Book 1, Page 383.
- A L.C.R.C. in Liber 2, Page 631 was recorded by Richard Steadman, P.S. #11370 on January 11, 1974. Corner is noted as, "Dug large hole, but found nothing; falls in muck area" re-established corner opposite fence East and on line with adjacent section corners. Set 3/4" iron pipe and cap for corner in Waverly Road. Witness: Nail and Tag in 6" Elm ENE 80.90 feet; E 1/4 Corner of Section 24, T2N, R3W, (Set 3/4" iron pipe & cap) is 65.92 feet North."
- An Act 132 survey recorded in Liber 5, Pages 22-23 was recorded by Kay Don Fluke, P.S. #18988 on August 14, 1986. Corner is noted as found 3/4" pipe in monument box recorded Liber 2, Page 631 (Act 74).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pipe in monument box. Monument falls 3' ± West of centerline Waverly Road and at fence line to the East. Measured North 65.82 feet to M-8, Eaton Eapids Township, T2N, R3W. Found no other witnesses. Accepted 3/4" pipe as corner set by Richard Steadman in A-4. Steadman appeared to set corner as an obliterated corner and this surveyor agrees with this method. Measured 2638.29 to A-7 and 2644.23 to A-9. From field traverse, determined corner to be on standard township line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 3/4" pipe in monument box and placed cap #28414 on pipe, witnessed by:
East 1/4 Corner, Section 24, T2N-R3W, North 65.82'
Set Nail and Tag #28414 West side Triple 8" Basswood S 15° E 187.17'
Set Nail and Tag #28414 South side 20" Elm N 40° E 108.40'
Set Nail and Tag #28414 North side 8" Box Elder N 80° E 49.74'

Signed by Maurice H. Mahieu
Surveyor's Michigan License No. 28414

Date 11-25-97

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 198
REVISED OCT., 199



P.A. 345 INGHAM COUNTY
PEER APPROVED 10/30/97 M