

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Liber 9 Page 293

For corners in AURELIUS TOWNSHIP

INGHAM COUNTY

Located In:

Corner Code #

- |                                    |         |                         |             |
|------------------------------------|---------|-------------------------|-------------|
| 1. Public Land Survey              |         | T <u>2N</u> R <u>2W</u> | <u>A-10</u> |
|                                    |         | T _____ R _____         | _____       |
|                                    |         | T _____ R _____         | _____       |
|                                    |         | T _____ R _____         | _____       |
| 2. Property Controlling in Section | S _____ | T _____ R _____         | _____       |
|                                    | S _____ | T _____ R _____         | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ | T _____ R _____         | _____       |
|                                    | S _____ | T _____ R _____         | _____       |

**FILED**

970047755  
 12/02/1997 13:38:34  
 REGISTER OF DEEDS  
 Paula Johnson  
 INGHAM COUNTY, MI

**Register of Deeds Stamp & File Number**

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Maurice H. Mahieu, in a field survey on September 26, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

- This corner was not set in the original GLO survey.
- On February 22, 1841 A. Jackson County Surveyor used corner. No mention of corner material. Witnesses Maple 18 in. N 33E 67 lks; R. Oak 28 in S 86E 27 1/2 lks. Survey recorded in Book 1, Page 46.
- On Feb. 10, 1852 A. Jackson County Surveyor used corner. No mention of corner material. Same witnesses as A-2.
- A L.C.R.C. recorded in Liber 2, Page 635 by Richard Steadman, P.S. #11370 on December 11, 1973 states "Dug large hold, but found nothing. Corner may have been destroyed by road construction. Re-established corner opposite fence line East and on line between adjacent section corners. Set 3/4" iron pipe for corner in Waverly Road. Witnesses: Nail and Tag in Twin 14" Walnut SW 66.18 feet; Nail and Tag in 7" Hickory WNW 45.67 feet; East 1/4 Corner of Section 25, T2N, R3W (Set 3/4" Iron Pipe and Cap) is 80.55 feet North".
- An Act 132 survey recorded in Liber 2, Page 686 by Richard Steadman, P.S. #11370 on April 14, 1976 states "3/4" pipe in monument box; Twin 14" Walnut SW 66.19'; 7" Hickory WNW 45.67'.
- An Act 132 survey recorded in Liber 4, Page 1278 by Hathaway J. Haynes, P.S. #5260 on July 29, 1986 states "3/4" pipe in monument box" gives no description of witnesses.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 3/4" iron pipe with damaged cap in monument box. Monument falls at intersection Waverly Road and fence line to the East. Found Nail and Tag #11370 South side Twin 14" Walnut, SW 66.18' and also measured North 80.54' to M-10, Eaton Rapids Twp., T2N, R3W. Richard Steadman, P.S. #11370 determined corner to be obliterated. Steadmans set corner is the correct location by using the occupied fence line to the East as evidenced. Accepted 3/4" pipe set by Richard Steadman as true location of corner. Measured 2689.51 to A-9 and 2636.76 to A-11. From field traverse work, determined corner to be on standard township line.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Found 3/4" pipe with illegible cap in monument box. Replaced cap with #28414.  
 Found Nail and Tag #11370 South side Twin 14" Walnut SW 66.18'  
 East 1/4 Corner, Section 25, T2N, R3W, North 80.54'  
 Set Nail and Tag #28414 North side 4" Basswood N 65° E 61.63'  
 Set Nail and Tag #28414 South side Wood fence post N 80° E 28.64'  
 Set Nail and Tag #28414 South side 24" Basswood N 75° W 39.55'  
 Set Nail and Tag #28414 East side 10" Walnut S 40° W 72.22'

Signed by Maurice H. Mahieu  
 Surveyor's Michigan License No. 28414

Date 11-25-97

